## FLUKE SIOA/AD



## **Instruction Manual**

FOR REFERENCE PURPOSES ONLY

Model

510 A/W

**AC Reference Standard** 

(33A1-12-10ZP-11)

P/N 313379

REV. 2 10/75

NOVEMBER 1971

### LIMITED WARRANTY

The JOHN FLUKE MFG. CO., INC., warrants each instrument it manufactures to be free from defects in material and workmanship under normal use and service for the period of one year from date of purchase. This warranty extends only to the original purchaser. This warranty shall not apply to fuses, disposable batteries (rechargeable type batteries are warranted for 90 days), or any product or parts which have been subject to misuse, neglect, accident or abnormal conditions of operations.

In the event of failure of a product covered by this warranty, John Fluke Mfg. Co., Inc., will repair and calibrate an instrument returned to an authorized Service Facility within one year of the original purchase; provided the warrantor's examination discloses to its satisfaction that the product was defective. The warrantor may, at its option, replace the product in lieu of repair. With regard to any instrument returned within one year of the original purchase, said repairs or replacement will be made without charge. If the fault has been caused by misuse, neglect, accident or abnormal conditions of operations, repairs will be billed at a nominal cost. In such case, an estimate will be submitted before work is started, if requested.

ANY IMPLIED WARRANTIES OF MERCHANTABILITY OR FITNESS SHALL BE LIMITED TO A PERIOD OF TWELVE MONTHS FROM THE DATE OF PURCHASE. THE FOREGOING WARRANTY IS IN LIEU OF ALL OTHER WARRANTIES, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO ANY IMPLIED WARRANTY OF MERCHANTABILITY, FITNESS OR ADEQUACY FOR ANY PARTICULAR PURPOSE OR USE. JOHN FLUKE MFG. CO., INC. SHALL NOT BE LIABLE FOR ANY SPECIAL, INCIDENTAL OR CONSEQUENTIAL DAMAGES, WHETHER IN CONTRACT, TORT OR OTHERWISE.

NOTE: Some states do not allow limitations on how long an implied warranty lasts, or the exclusion or limitation of incidental or consequential damages, so the above limitations or exclusion may not apply to you. This warranty gives you specific legal rights, and you may also have other rights which vary from state to state.

#### If any fault develops, the following steps should be taken:

- 1. Notify the John Fluke Mfg. Co., Inc. or nearest Service facility, giving full details of the difficulty, and include the Model number, type number, and serial number. On receipt of this information, service data or shipping instructions will be forwarded to you.
- 2. On receipt of the shipping instructions, forward the instrument, transportation prepaid. Repairs will be made at the Service Facility and the instrument returned, transportation prepaid.

#### SHIPPING TO MANUFACTURER FOR REPAIR OR ADJUSTMENT

All shipments of John Fluke Mfg. Co., Inc., instruments should be made via United Parcel Service or "BestWay\*" prepaid. The instrument should be shipped in the original packing carton; or if it is not available, use any suitable container that is rigid and of adequate size. If a substitute container is used, the instrument should be wrapped in paper and surrounded with at least four inches of excelsior or similar shock-absorbing material.

#### CLAIM FOR DAMAGE IN SHIPMENT TO ORIGINAL PURCHASER

The instrument should be thoroughly inspected immediately upon original delivery to purchaser. All material in the container should be checked against the enclosed packing list. The manufacturer will not be responsible for shortages against the packing sheet unless notified immediately. If the instrument is damaged in any way, a claim should be filed with the carrier immediately. (To obtain a quotation to repair shipment damage, contact the nearest Fluke Technical Center.) Final claim and negotiations with the carrier must be completed by the customer.

The Journal Me Mfg. Co., Inc. will be happy to answer all application or use questions, which will enhance your use of this instrument. Ple see a ground requests or correspondence to: JOHN FLUKE MFG. CO., INC., P.O. Box 43210, MOUNTLAKE TERRACE, WALL STO., 198043, Atten: Sales Dept. For European Customers: FLUKE (Nederland) B.V., Zevenheuvelenweg 53, Tilburg, The Netherlands,

John Fluke Mfg. Co., Inc. ● P.O. Box 43210 ● Mountlake Terrace, Washington 98043

<sup>\*</sup> For European customers, Air Freight prepaid.

THIS DOCUMENT CONTROLS SPECIFICATIONS AND FABRICATION OF A SPECIAL INSTRUMENT MANUFACTURED BY THE JOHN FLUKE MANUFACTURING COMPANY, INCORPORATED.

MODEL 510A/AD

	FLUKE JOHN FLUKE MFG CO., INC.	
	SPECIFICATION CONTROL DRAWING SPECIAL PRODUCTS DIVISION	510A
PROJ. ENGRED Jacon Land, DATEZ-3-72.		AI
MKTG. DATE 2- 7, 75	510A/AD-130	13
ENG. APPD. A. D. DATE 2-3-72		0
11 H 16 1 3-5-7.	JF NO.257915 NO. OF PAGES 6 REV. 22	

DOCUMENT CHANGE RECORD								
REV. LTR.	PAGE	DESCRIPTION OF CHANGE						
1	4	Delete: Item 10  Add: Items 13, 15, 18 & 19  Correct: Dwg. number on Items; 14 from 3001 to 3003 16 from 4001 to 4003 17 from 4002 to 4004	GAN DAS					
	5	Correct: Item 1, sheets from 2 to 3  Add: Item 2  Correct: Item 3, Dwg. number from 510A/AA-6001 to 510A/AN-8001 and add Purchased Part comments.	0					
			DB 12-28-3					
2	4	Remove MFG usage for Item 1	12 28-3					
	5	Add Item 7 Test Procedure changed from -160 to -150	}					
<b></b>	6	Test Procedure Changed Lion -100 to 150	,					
		JOHN FLUKE MANUFACTURING CO	D., INC.					
		510A/AD	REV PAGE					

- 1.0 GENERAL Similar to 510A-04 with the following exceptions:
  - 1.1 Capable of being phase locked to an external 400Hz 26V RMS reference.
  - 1.2 Provides two separate transformer isolated outputs at 10V RMS into 100K ohms.
  - 1.3 Housed in 3-1/2 inch high full rack width package.
- 2.0 ELECTRICAL All electrical specifications apply with each output loaded into 100K ohms.
  - 2.1 Phase reference input: 26V RMS ± 10%, 380 to 420Hz, 30K ohm input impedence.
  - 2.2 Outputs: Two, transformer coupled, at 10V RMS ± .05%. Phase relationship to phase reference input 0 ± 1 degree. Total harmonic distortion: < 0.15%. Isolation between any two outputs or input to any output: 300V DC or peak AC; 1100 pf maximum capacitance.</p>

#### 3.0 MECHANICAL

- 3.1 Chassis size 3-1/2 inch high, 19 inches wide (rack mountable), 15-1/2 inch depth behind front panel.
- 3.2 Input and output binding posts on 3/4 inch centers located on rear panel.
- 3.3 Overload indicator on front panel.
- 4.0 PARTS LIST See Bills of Material and Engineering Drawings listed in Section 5.2 MFG Column.

#### 5.0 DOCUMENTATION

5.1 Standard 510A Manual with 510A/AD-130 Specification Control Drawing and Drawings listed in Section 5.2 MNLS Column.

JOHN FLUKE MANUFACTURING CO., INC.

510A/AD ~ 130

REV PAGE
3

		5.2 D	OCUMENTATION INDEX						N	IODEL	. 51	0A,	/AE	
	ITEM	DRAWING NUMBER	DRAWING TITLE		SHEETS	B/MTL	MFG		GE					
	1	510A/AD-160	Acceptance Test Procedure					x						
	2	510A/AD-1001	Schematic Output AC Ref Std.		1		х	х						
	3													
	4	510A/AD-2001	Front Panel Punch	·	1		x				· · · · · · · · · · · · · · · · · · ·	·		
	5	510A/AD-2002	Rear Panel Punch		1		x							
	6	510A/AD-2003	Front Panel Screen	ed	1		x							
	7	·510A/AD-2004	Rear Panel Screene	d	1		x			_				· .
	.8	510A/AA-2005	Inner Panel LH		1		x							
	9	510A/AA-2006	Inner Panel RH	<del>,,,</del>	1		x		_					·
NAME OF THE OWNER, OWNE	10								$\bot$					
	11	510A/AA-2008	Hold Down, Transfe	ormer	1		X.		_					
	12	510A/AA-2009	Pad, Transformer	Mtg.	1		х		_					
	13	510A/AA-2010	Support		1		Х		_					
	14	510A/AA-3003	Drill Detail Phase Lock PCB As	ssy.	2		х							
	15	510A/AA-2011	Support		1		Х		_			·		
	16	510A/AD-4003	Phase Lock PCB As	ssy.	1	х	х	х				٠.		
	17	510A/AN-4004	Main PCB Assy. (Modification)		1	x	Х	x	_	-			<u>i</u>	
	18	510A/AA-2012	Support		ı		х		_					
	19	510A/AA-2013	Support		<u>1</u>		X							
	20	<u></u>		<u> </u>										
				JOHN FL	UKE	. N	14	1U !	FÁC	TURI	NG			PAGE
Manage Commercial Comm				510A	/AI	)- <u>]</u>	30						) 	4.

<u></u>	5.2 D	OCUMENTATION INDEX				an aba			DEL: 510A/AD
ITEM	DRAWING NUMBER	DRAWING TITLE	SHEETS	B/MTL		MNLS	GE		
1	510A/AD-5001	Final Assy.	3	x	Х				
2	510A/AA-6510	Power Transformer	1.		x				0770
3	510A/AN-8001	8 Output Ratio Transformer	2		x				OECO 17534 (Purch)
4				_					
5	510A/AD	Test & Button-up	1	$ \mathbf{x} $	Х		_		
6				_	-				
7	510A/AD-150	Production Test Procedu	ıе	-	Х	-			
8				<u> </u>	_		_		
9			-	-	-	_		_	
10			_	-	_	-	-		
11		·		-	┡	-	-	_	
12	4		-	-	_	ļ	ig	ļ	
13			-	+	1	igg	-	-	
14			<u> </u>	_	-	+	$\downarrow$	_	
15				$\bot$	-	+	-	1	
16			-	+	1	-	+		
17	7		-	-	+	_	_	+	
18	3		-	$\perp$		+	-	+	
19	9		-	+			-	-	
20	o l							1	TURING CO., INC.
_	Applicable Dra	wings					J F /		REV PAC
	•	510A	/AI	) l	30				2-15

WEETER ST

d A

精整

6.0 TEST PROCEDURE - See 510A/AD-150.


JOHN FLUKE MANUFACTURING CO., INC.

510A/AD-130


REV PAGE

PHASE LOCK PCB ASSEMBLY
DWG. 510A/AD-1001

IZ3
456
X78



(N




ľ

A service of the serv

# PROPRIETARY NOTICE .

This document and the technical data normon described, are proprietary to John Fluke Mig. Co., Inc., and shall, not, without express written permission of John Fluke Mig. Co., Inc., be used, released or discipled in the same of the solical quotal tions from a competitive source or used for manufacture by anyone either than John Fluke Mig. Co., Inc., The information therefore has been developed at John The information and for facorporation into anyone entire wall for facorporation into the specifications and other documents which specify procurement of products from John Fluke XC.

89536 FOXXX ± 020



## Change/Errata Information

Issue No: 3

This change/errata contains information necessary to ensure the accuracy of the following manual. Enter the corrections in the manual if either one of the following conditions exist:

- The instrument's pcb revision letter is equal to or higher than that which is indicated at the beginning of the change.
- No revision letter is indicated at the beginning of the change/errata.

#### MANUAL

Title:

MODEL 510A AC REFERENCE STANDARD

Print Date:

**NOVEMBER 1971** 

**Rev and Date: 2 – 11/75** 

#### C/E PAGE EFFECTIVITY

Page No.		Print Date
1	,	2/79
2		6/79

#### CHANGE #1-8993

On page 5-7, change the stock no of diode CR1 from 309617 to 428623.

#### CHANGE #2-11381

On page 5-10, delete Q26 from the REF DESIG column Q17, Q26 and change the tot qty from 2 to 1. Add the new entry: Q26; Tstr, Si; 477695; 1; 1.

On page 5-28, add the listing 477695; 07910; 02377.


#### CHANGE #3-12151

Rev. -B, A3 Rechargeable Battery Kit (-01 Option)


On page 5-23, make the following changes:

FROM: Q3, Q6/Tstr, Semicon, germanium PNP/148619/2/1 TO: CR6, CR7/Diode, Germanium, 80 mA/149187/2/1

On page 5-22, Figure 5-12, and page 6-1, Figure 6-1, replace the PCB with the following:



On page 8-3/8-4, Figure 8-1 (Detail 1, A3 Battery Pack PCB) make the following changes:



#### 510A

#### CHANGE #5 - 12285

Rev.-C, Al Front Panel Assembly (510A-4051)

On page 5-7, make the following changes:

FROM: Decal, Front Panel /309351/1
TO: Decal, Front Panel/508234/1
ADD: J4/Binding Post, Green/275586/1

Rev.-B, A4 Rear Panel Assembly (510A-4052)

On page 5-25, make the following changes:

FROM: J2/Binding Post, White/275586/1 TO: J2/Binding Post, Green/275586/1

DELETE: Decal/313064/1

#### ERRATA#1

On page 1-1, under SPECIFICATIONS, add the following information:

Protection Class . . . . #1 (Relates solely to insulation or grounding properties further defined in IEC 348.)

# Table of Contents

SECTION		TITLE	PAGE
1	INTROD	UCTION AND SPECIFICATIONS	1-1
	1-1.	Introduction	1-1
	1-6.	Specifications	1-1
2	OPERATI	ING INSTRUCTIONS	2-1
	2-1.	Introduction	2-1
	2-3.	Shipping Information	2-1
	2-6.	Input Power	2-1
	2-8.	Installation	2-1
	2-10.	Operating Features	2-1
	2-12.	Operating Notes	2-1
	2-22.	Operating Procedures	2-3
	2-25.	Applications	2-4
3	THEORY	OF OPERATION	3-1
	3 <b>-1</b> .	Introduction	3-1
	3-3.	Block Diagram Analysis	3-1
	3-7.	Circuit Descriptions	3-2
6	OPTION ,	AND ACCESSORY INFORMATION	6-1
	6-1.	Introduction	6-1
	6-3.	Option Information	6-1
	6-5.	Accessory Information	6-1
	RACK MO	OUNTING FIXTURES	6-1
	6-1.	Introduction	6-1

(Continued on page ii)

#### TABLE OF CONTENTS, continued

SECTION	TITLE	PAGE
5	LIST OF REPLACEABLE PARTS	. 5-1
	5-1. Introduction	
	5-4. Parts List Column Descriptions	5-1
	5-5. Manufacturers' Cross Reference List	
	Column Descriptions	. 5-2
	5-6. How to Obtain Parts	5-2
	5-9. Serial Number Effectivity	5-3
6	OPTION AND ACCESSORY INFORMATION	6-1
	6-1. Introduction	
	6-3. Accessory Information	6-1
	6-5. Option Information	6-1
	RACK MOUNTING FIXTURES	
	KACK MOUNTING FIXTURES	6-1
	6-1. Introduction	6-1
	OPTION -01 RECHARGEABLE BATTERY PACK	6-1
	6-1. Introduction	6-1
	6-3. Installation	
		0-2
7	GENERAL INFORMATION	7-1
8	SCHEMATIC DIAGRAMS	8-1

## List of Illustrations

FIGURE	TITLE	PAGE
1-1	Typical Short Term Stability	1-2
1-2	Total Harmonic Distortion	1-3
1-3	Load Regulation	1-3
1-4	Outline Drawing	1-4
2-1	Operating Features	2-2
2-2	Load Connections	2-3
2-3	Automated Test System AC Reference	2-4
2-4	Model 510A/AA Block Diagram	2-4
3-1	Model 510A Block Diagram	3-1
3-2	Peak AC to DC Converter (Simplified)	3-4
4-1	Adjustment and Test Point Locations	4-3
4-2	Assembly Locations (Bottom Cover Removed)	4-3
4-3	Load Regulation	4-4
4-4	DC Reference Equipment Connections	4-6
4-5	Thermal Transfer Equipment Connections	4-7
4-6	DC Reference Equipment Connections	4-8
4-7	Thermal Transfer Equipment Connections	4-10
4-8	V <sub>REF</sub> Jumper Locations	4-10

200

#### ${\bf LIST\ OF\ ILLUSTRATIONS}, continued$

FIGURE	. TITLE	PAGE
4-9	Operating Voltage Check Points	4-11
4-10	A3 Battery Pack PCB Checks	4-12
4-11	Circuit Isolation Checks	4-13
5-I	AC Reference Standard	5 <b>-</b> 4
5-2	Front Panel Assembly	5-6
5-3	Main PCB Assembly	5 <b>-</b> 8
5-4	PCB Assembly, 50 Hz (-02 Option)	5-14
5-5	PCB Assembly, 60 Hz (-03 Option)	5-15
5-6	PCB Assembly, 400 Hz (-04 Option)	5-16
5-7	PCB Assembly, 1000 Hz (-05 Option)	5-17
5-8	PCB Assembly, 2400 Hz (-06 Option)	5-18
5-9	PCB Assembly, 5000 Hz (-07 Option)	5-19
5-10	PCB Assembly, 19.2 kHz (-08 Option)	5-20
5-11	PCB Assembly, 100 kHz (-09 Option)	5-21
5-12	Rechargeable Battery Kit (-01 Option)	5-22
5-13	Rear Panel Assembly	5-24
6-1	Rack Mounting Configurations	6-1
6-2	Rack Ear Installation	6-2
6-3	Dual, Triple and Quad Mount	6-3
6-1	510A-01K Battery Pack	6-1
6-2	Battery Pack Kit Locations	6-2

# List of Tables

TABLE	TITLE							
1-1.	Standard Frequencies and Accuracy			1-1				
4-1.	Required Test Equipment		•	4-2				
4-2.	Output Amplitude Accuracy		•	4-5				
12	A & R Tumper Selection			4-11				

#### Section 1

## Introduction & Specifications

#### 1-1. INTRODUCTION

1-2. The Model 510A is a precision ac reference standard. It produces a fixed frequency output having an amplitude of 10V rms. Standard frequencies and accuracies are given in Table 1-1. Other frequencies are available upon special request. The center frequency can be varied  $\pm 1\%$  with a control on the front panel. Frequency resolution with this control is better than  $\pm 0.05\%$ .

Table 1-1. STANDARD FREQUENCIES AND ACCURACY

24 HOUR ACCURACY	30 DAY ACCURACY	STANDARD FREQUENCY
±0.01%	±0.015%	50 Hz, 60 Hz, 400 Hz, 1 kHz, 2.4 kHz, 5 kHz, 19.2 kHz
±0,04%	±0.05%	100 kHz

- 1-3. Output current is fully protected from overloads and short circuits. Maximum load current for rated accuracy is 10 mA. Visual indication of an overload is provided by a light emitting diode (LED) on the front panel. Two sets of parallel connected binding posts on the front and rear panel provide load connection.
- 1-4. The ac reference standard can be operated from line power or it can be battery powered through an optional rechargeable battery pack. Line voltage requirement is 115/230 vac, 50 to 500 Hz, single phase. The rechargeable battery pack is available as the -01 Option. It allows at least 16 hours of continuous operation without line power. Battery charging is done whenever line power is applied.
- 1-5. The Model 510A is designed for bench top use or it can be installed in a standard 19 inch equipment rack. Rack mounting kits are available as accessories to permit single, dual, triple, and quadruple side-by-side rack installation

#### 1-6. SPECIFICATIONS

Any single fixed frequency from 50 Hz to 100 kHz. Standard frequencies are: 50; 60; 400; 1,000; 2,400; 5,000; 19,200 and 100,000 Hcrtz.

Amplitude Accuracy	24 Hours	30 Days	90 Days
50 Hz - 20 kHz	±0.01%	$\pm 0.015\%$	±0.02%
20 kHz - 50 kHz	±0.015%	±0.025%	±0.035%
50 kHz — 100 kHz	±0.04%	$\pm 0.05\%$	±0.06%

Above accuracy applies after 10 minutes warmup, operating temperature of  $23 \pm 2^{\circ} \text{C}$ , and includes worst case deviations of the output caused by line, load, stability, and noise conditions. Assumes calibration against an AC-DC transfer standard with an AC-DC difference of 50 ppm from 50 Hz to 50 kHz and 300 ppm from 50 kHz to 100 kHz.

Amplitude Accuracy Using DC Calibration . . .

Using a DC reference accurate to  $\pm 15$  ppm and standard laboratory equipment, the 510A may be calibrated to achieve the following accuracies at standard operating temperatures of  $23 \pm 2^{\circ}$ C, and worst case deviations caused by line, load, stability and noise conditions.

							30 Days	90 D	
50  Hz - 5  kHz .							+0.01%	±0.00	2%
5  kHz - 10  kHz .							±0.02%	±0.03	
10 kHz - 30 kHz.							±0.05%	±0.0°	
30 kHz – 100 kHz					٠		<u>+</u> 0.15%	<u>+</u> 0.1	7%
Amplitude Stability .					٠	- <del></del>		30 Days	90 Days
50  Hz - 20  kHz								±0.005%	±0.01%
20 kHz - 100 kHz						<u>+</u> 0	.004%	±0.01%	±0.02%




Figure 1-1. TYPICAL SHORT TERM STABILITY

AMPLITUDE NOISE	Amplitude deviation due to noise is less than 20 ppm peak- to-peak through a 1 Hz bandwidth over a 1 minute interval.
AMPLITUDE TEMPERATURE COEFFICIENT	$\underline{15^{\circ} - 50^{\circ}C} \qquad \underline{0^{\circ} - 15^{\circ}C}$
50 Hz – 5 kHz	5 ppm/°C 12 ppm/°C
5 kHz – 10 kHz	7 ppm/°C 15 ppm/°C
10 kHz - 30 kHz	10 ppm/°C 17 ppm/°C
30  kHz - 100  kHz	15 ppm/°C 22 ppm/°C

510A TOTAL HARMONIC DISTORTION . . . . . . (See Figure 1-2). CENTER FREQUENCY ACCURACY...... ±0.1% ±0.05% using front panel vernier FREQUENCY VERNIER . . . . . . . Screwdriver adjustment, ±1% of center frequency 500 ppm per month Frequency Temperature Coefficient . . . . Less than 150 ppm/°C Common Mode Rejection is defined as the affect on the rms or average value of the 10V rms output due to a common mode signal between the low terminal and chassis. This rejection is: Greater than 100 db for common mode signals from 1 Hz to 500 Hz, 10V peak-to-peak maximum. Greater than 70 db for common mode signals from 500 Hz to 1 MHz, 3V peak-to-peak maximum. Maximum allowable dc potential between output low and chassis ground is 100 volts. LOAD REGULATION . . . (See Figure 1-3). PERCENT 510A HARMONIC DISTORTION VS FREQUENCY 510A LOAD REGULATION NO LOAD TO FULL LOAD (0-10MA) REGULATION DISTORTION RMAN 0 <del>| . . . . .</del> 50 Hz 100 Hz

Figure 1-2. TOTAL HARMONIC DISTORTION

1000 Hz

FREQUENCY

10 kHz

100 kHz




Figure 1-3. LOAD REGULATION

LINE REGULATION . . . . . < 10 ppm, ±10% line change **OUTPUT CONNECTIONS** High, Low and Chassis binding posts on front and rear panels. UNCALIBRATED INDICATION . . . . . . . . . . . . . Front panel display labeled "UNCAL" indicates when load **ENVIRONMENTAL** exceeds 10 mA. Operating Temperature Range . . . . . . . 0°C to 50°C -40°C to +75°C; -40°C to +60°C with batteries Humidity Range . . . . . . . . . Up to 80% relative humidity, 0°C to 35°C Up to 70% relative humidity, 35°C to 50°C 20g, 11 millisec half-sine wave 4.5g, 10 Hz -- 55 Hz 0 to 10,000 feet - Operating 50,000 feet - Non-Operating An optional rechargeable battery pack will power the AC 115/230V ac  $\pm 10\%$ , 50 - 500 Hz, Single Phase Reference Standard for 16 hours. The battery pack is field installable. 3-1/2" high x 4-1/4" wide x 12" deep Up to four 510A's can be mounted side by side and installed in a standard 19" EIA rack with optional accessory ears.




Figure 1-4. OUTLINE DRAWING

#### Section 2

## Operating Instructions

#### 2-1. INTRODUCTION

2-2. This section contains operating instructions for the Model 510A. If any difficulties are encountered, contact the nearest John Fluke Sales Representative or write directly to the John Fluke Mfg. Co., Inc. Please include the instrument serial number when writing.

#### 2-3. SHIPPING INFORMATION

- 2-4. The Model 510A was packaged and shipped in a foam packed cardboard carton. Upon receipt, a thorough inspection should be performed to reveal any damage in transient. Special instructions for inspection and claims are included in the carton.
- 2-5. If reshipment is necessary, the original container should be used. If the original container is not available, a new one can be obtained from the John Fluke Mfg. Co., Inc. Please reference the Model number when requesting a new container.

#### 2-6. INPUT POWER

2-7. This instrument can be operated from either a 115 or 230V ac, 50 to 500 Hz, single phase power line. A slide switch on the rear panel allows selection of the appropriate line voltage. The rated value of the rear panel fuse F1 is as follows:

115 VAC 1/4A, 3AG

230 VAC 1/8A, 3AG

#### 2-8. INSTALLATION

2-9. The Model 510A is designed for bench-top use or it

can be installed in a standard 19 inch equipment rack with Accessory rack mounting brackets. Up to four units can be rack mounted in side-by-side positions. Rack installation procedures are located in Section 6.

#### 2-10. OPERATING FEATURES

2-11. The location and function of all controls, connectors, and indicators is shown in Figure 2-1.

#### 2-12. OPERATING NOTES

#### 2-13. AC Line Connection

2-14. The input power cord has a three prong, polarized connector. This plug allows connection to either a 115 or 230V ac, 50 to 500 Hz, single phase power line. The round pin connects the chassis to earth ground; therefore, ensure that the round pin is connected to a high quality earth ground. The instrument is energized through a POW-ER switch on the front panel. A front panel meter indicates LINE OPR when the instrument is energized.

#### 2-15. Battery Power (-01 Option)

#### NOTE

Battery manufacturers recommend that nickel-cadmium batteries should not be stored for extended periods of time without recharging at least every 90 days. Storage temperatures below 25°C are recommended.

2-16. When the -01 Option is installed, the Model 510A can be operated from an internal rechargeable battery. Battery operation is activated by disconnecting the power




Figure 2-1. OPERATING FEATURES (1 of 2)




Figure 2-1. OPERATING FEATURES (2 of 2)

cord from line power and turning the instrument on with the POWER switch on the front panel. Relative state of charge (BAT OK) is indicated by a meter on the front panel. The battery is automatically charged whenever the instrument is operated from line power.

#### NOTE!

The chassis of the instrument and the  $\frac{1}{2}$  terminal are connected to ground through the power cord. When battery operation is used and the chassis is isolated from ground, this ground connection will be broken.

#### 2-17. Load Connections

- 2-18. Output load connection is done using HI and LO OUTPUT terminals on the front or rear panel. These OUTPUT terminals are parallel connected and only one set should be connected to a load at one time. A  $\frac{1}{2}$  terminal is included for convenient connection to ground (see preceding note). Maximum allowable potential between the LO OUTPUT and  $\frac{1}{2}$  terminal is 100V dc.
- 2-19. The following rules should be observed for all load connections.
- a. AC power to the Model 510A and associated equipment should be derived from the same power line.
   Line power connections should be as close together as possible.
- b. Shielded, twisted pair load cables should be used.

  Typical load connections are shown in Figure 2-2.
- c. Load cables should be kept as short as possible. Maximum lead resistance should be less than 20  $m\Omega$ .

#### 2-20. Overload Protection

2-21. The maximum output current is limited by the power capability of the internal circuitry. This circuitry will not be damaged even if the OUTPUT terminals are short circuited. However, when the output current exceeds 10 mA, the output will not be within its specified accuracy. Visual indication of an output current greater than 10 mA is provided by an UNCAL lamp (LED) on the front panel.

#### 2-22. OPERATING PROCEDURES

2-23. The Model 510A produces a fixed frequency output having an amplitude of 10V rms. Frequency accuracy is




Figure 2-2. LOAD CONNECTIONS

 $\pm 0.1\%$ , adjustable  $\pm 1\%$  with a FREQUENCY VERNIER on the front panel. Amplitude accuracy is given in Section 1.

- 2-24. To operate the instrument, proceed as follows:
- a. Connect the power cord to line power. See paragraph 2-6 and 2-13.
- b. Make the desired load connections at the front or rear panel OUTPUT terminals.
- c. Set the POWER switch to ON and allow the instrument to operate for ten minutes. The meter on the front panel should indicate LINE OPR and the UNCAL indicator should be out.
- d. After ten minutes of operation, the output is at its specified accuracy.

#### NOTE!

Battery operation (-01 Option) is described in paragraph 2-15.

#### 2-25. APPLICATIONS

#### 2-26. Introduction

2-27. The Model 510A can be used in a number of ways as a precise ac reference. The following paragraphs describe a few of its applications.

## 2-28. Precision AC Source for Automatic Test Systems

2-29. Automated test systems containing Fluke 4200 series voltage sources can use the Model 510A as an external reference to produce precise ac voltages. Figure 2-3 shows such a system. System ac output is from 0 to 45V ac rms at up to 0.7 amperes rms. Overall system accuracy of  $\pm 0.02\%$  can be achieved for frequencies up to 5 kHz.




Figure 2-3. AUTOMATED TEST SYSTEM AC REFERENCE

#### 2-30. Phase Locked AC Reference Standard

2-31. A Model 510A can be modified to phase lock with an external signal and provide multiple outputs. Figure 2-4 shows the modified Model 510A/AA which is designed to synchronize with an external 400 Hz signal and provide eight transformer coupled outputs. Programmable phase reversal at each output is also provided. The outputs can be used as external references in the system application described in paragraph 2-28. Typical specifications for the Model 510A/AA are as follows:

FREQUENCY	400 Hz ±5% (other frequencies can be specified)
OUTPUT VOLTAGE	10V rms (eight outputs, transformer coupled)
OUTPUT ACCURACY	±0.1%
OUTPUT PHASE RELATIONSHIP	0° ±1° or 180° ±1° (program- mable
TOTAL HARMONIC DISTORTION	0.2%
PHASE LOCK CAPTURE RANGE	±5% about center frequency
SYNC INPUT VOLTAGE	24V rms




Figure 2-4. MODEL 510A/AA BLOCK DIAGRAM

#### Section 3

# Theory of Operation

#### 3-1. INTRODUCTION

3-2. This section contains the theory of operation for the Model 510A. The information is arranged under headings of "BLOCK DIAGRAM ANALYSIS and CIRCUIT DESCRIPTIONS." It is recommended that this section be thoroughly read and understood before any attempt is made at servicing this instrument.

#### 3-3. BLOCK DIAGRAM ANALYSIS

3-4. The Model 510A produces an extremely stable 10V rms signal at a fixed frequency. Five major circuits are used to produce and control the output. These circuits and their interconnection are shown in Figure 3-1.

3-5. The DC Reference Supply produces an accurate, low temperature coefficient, dc voltage of +14.14214V. This voltage is applied to one end of a divider at the input of the Peak AC to DC Convertor and also functions as a reference for the -18V Regulator. The other end of the divider receives the 10V rms output of the Model 510A, thus producing a OV condition at its center when the peak of the output signal is equal to minus the Reference Supply voltage. The Peak AC to DC Convertor produces an amplified signal that is equal to the negative difference between the output signal and the +14.14214V reference. This signal charges a capacitor at the output of the Peak AC to DC Convertor which is then transferred to a capacitor at the input of the Integrator by the Sample and Hold. Transfer is done only during the positive peak excursion of




Figure 3-1. MODEL 510A BLOCK DIAGRAM

the signal. The Integrator produces a dc output proportional to the time integral of the voltage stored on its input capacitor. This dc output is applied to the Oscillator where it causes the peak output amplitude to maintain a near OV condition at the input to the Integrator. The Overload Detector monitors the output of the Model 510A and turns on the UNCAL indicator when the output current exceeds 10 mA.

3-6. All operating voltages are produced by the ±18V DC Regulators. Reference voltage for the +18V DC Regulator is derived from the -18V DC Regulator. The -18V DC Regulator receives a reference voltage from the Reference Supply. Unregulated inputs to each regulator are derived from the Rectifier or the -01 Option Battery Pack. The Battery Pack operates in the absence of line power to the Rectifier. Relative charge state of the batteries is indicated by a meter connected across the +18V DC Regulator. A rectifier located in the -01 Battery Pack circuitry provides recharging of the batteries whenever line power is applied.

#### 3-7. CIRCUIT DESCRIPTIONS

3-8. The following paragraphs describe the circuitry in the Model 510A. Each description is keyed to the schematic diagram located at the rear of the manual.

#### 3-9. Input Power

AC line power from A4J1 is applied to A4T1 3-10. throught the POWER switch A1S1A and the 115/230 slide switch A4S1. The primary of A4T1 consists of two windings which are interconnected through A4S1 for operation from either a 115 or 230V ac line. Parallel connection is used for 115V ac line operation while series connection is used for 230V ac line operation. Both primary windings are completely shielded to reduce capacitive coupling between the power line and the floating circuitry in the instrument. The shield is connected to chassis ground and power line ground through the power cord. The secondary of A4T1 consists of two separate windings both of which are shielded to eliminate the generation of common mode signals that could appear at the OUTPUT terminals. This shield is connected to the center-tap of a secondary winding and power supply common. The center-tapped secondary winding provides ac power to rectifiers CR2 and CR3, CR4. The other secondary winding supplies ac power to the Battery Pack PCB (-01 Option) and the meter, A1M1. Diode CR1 rectifies the ac voltage present during line operation to provide a full-scale LINE OPR indication on A1M1. A2DS1 and DS2 function to stabilize and limit the maximum current used by the Battery Pack PCB during charging of the batteries.

#### 3-11. A3 Battery Pack

3-12. The A3 Battery Pack is installed as the -01 Option. It consists of a Battery Pack PCB and two batteries, BT1 and BT2. This circuitry provides operation from the batteries in absence of line power, disconnects the batteries when they are in a low charge-state to prolong battery life, limits the maximum battery current drain should a circuit malfunction occur, and disconnects the batteries from the instrument circuitry and recharges them during line operation.

BATTERY OPERATION. When line power is re-3-13. moved and the POWER switch is ON, the batteries BT1 and BT2 are connected to the inputs of the ±18V Regulators through the Battery Pack PCB. The positive output of BT1 is applied through S1B to J5 where a divider consisting of R2, CR3 and R4 supplies the base of Q2 with a positive voltage. This voltage turns on Q2 which supplied base current to Q1 and also turns it on. Conduction of Q1 applies the positive output of BT1 through the series transistor Q3 to the input of the +18V Regulator. The diode connection of Q3 prevents reverse current flow from the +18V Regulator to the battery. The negative output of BT2 is applied through S1C to the series transistors Q5. Since a positive voltage is available at the emitter of Q4 through R8, Q4 is turned on in sequence with the conduction of Q1. This condition turns on Q5 and applies the negative output of BT2 through the series transistor Q6 to the input of the -18V Regulator. The diode connection of Q6 prevents reverse current flow from the -18V Regulator to the battery.

3-14. Should the batteries discharge to a state where they can no longer furnish adequate power, the series transistors Q1 and Q5 are automatically switched off. This is made possible through the use of zener diode CR3. As the output of BT1 decreases, the voltage at the base of Q2 reaches a point where the transistor can no longer furnish enough base current for Q1 to maintain conduction. O1 is therefore cut-off and disconnects the output of BT1 from the -18V Regulator. Sharp cut-off for Q1 is ensured by R6 which provides some of the base current for Q2. Once the voltage at the collector of Q1 begins to drop, base current to Q2 is further reduced, this sharply cuttingoff Q1. Since the conduction of Q4 and Q5 is slaved to the conduction of O1, as described in the preceding paragraph, the negative output of BT2 is also disconnected from the -18V Regulator.

- 3-15. The maximum current drain from the batteries is limited by the selection of the value of R5 and R9. These resistors limit the maximum base current to Q1 and Q5. Should a short circuit appear at either output, the maximum current is therefore dependent upon the base current of Q1 or Q5 times their current gain.
- 3-16. LINE OPERATION. When line power is applied, the batteries are disconnected from the ±18V Regulators and are recharged. Battery disconnection is caused by a -22V battery disconnect voltage produced by CR3, CR4 and C1. This voltage is applied to a divider consisting of R3 and R4 in the Battery Pack PCB. Presence of a negative voltage at the base of Q2 turns it off and causes Q1 to turn off. Since Q4 and Q5 are slaved to Q1, they are also turned off and both batteries are disconnected from the ±18V Regulators. Diodes CR4 and CR5 limit the maximum negative base and emitter voltage at Q2 and Q5 during line operation.
- 3-17. Charging of the batteries is provided through full-wave rectifier CR1 in the Battery Pack PCB. AC power for this rectifier is derived from the untapped secondary of T1. A2DS1 and DS2 function as a ballast to limit the maximum charging current. Zeners CR2 and CR6 in the Battery Pack PCB limit the maximum battery voltage during charging.

#### 3-18. ±18V Regulator

- 3-19. The  $\pm 18V$  Regulators produce low ripple operating voltages for the instrument. Input voltage to the regulators is derived from full-wave rectifiers when the instrument is line powered or from batteries if the -01 Option is installed. The -18V Regulator receives its reference from the Reference Supply. Reference voltage for the +18V Regulator is derived from the -18V Regulator; thus, should any malfunction occur in one supply, all will be affected.
- 3-20. +18V REGULATOR. The +18V Regulator consists of Q1 through Q3. Q1 is the series-pass element. Q2 and Q3 control the base current of Q1 to maintain the +18V dc output. Resistor R3 ensures initial turn-on of Q2 and Q3. The base of Q3 is referenced to the -18V Regulator through R10 and receives a sample of the +18V dc output through R8 and R9. Any change in the +18V dc output is therefore amplified by Q2 and Q3, which then alters the conduction of Q1 to maintain the regulated output. Variable resistor R9 allows adjustment of the +18V dc output.
- 3-21. -18V REGULATOR. The -18V Regulator consists of Q4 through Q6. Q4 is the series-pass element. Q5 and Q6 control the base current of Q4 to maintain the -18V dc output. R12 ensures initial turn-on of Q5 and Q6.

The base of Q6 is referenced to the Reference Supply (V<sub>REF</sub>) through R18, CR5, and CR6 and receives a sample of the -18V dc output through R17. CR5 and CR6 compensate for the voltage temperature coefficient at the base of Q6 as well as its base emitter voltage drop. Output voltage from this supply is therefore dependent upon V<sub>REF</sub> and the ratio of R17 to R18.

#### 3-22. Reference Supply

The Reference Supply produces an extremely stable reference voltage (VREF) upon which the accuracy and stability of the rms output is based. It consists of a high gain, high input impedance, differential amplifier U1 and a reference amplifier U2. The temperature coefficient of the base/emitter voltage for U2 is accurately matched to the temperature coefficient of the zener element through factory selection of R22 and R23. Output voltage of this supply is scaled to +14.14214V dc through selection of R30 and R31. Variable resistor R27 allows adjustment of VREF. The adjustment range of R27 is compensated through jumper selection of R25 and R29. The resulting stable reference at the collector of U2 is applied to the non-inverting input of U1. The other input to U1 receives an equivalent voltage from the divider composed of R20 and R21. Any change in V<sub>REF</sub> is sensed at the base of U2 which produces an amplified change at the non-inverting input to U1. This change then alters the conduction of U1 such that VREF is maintained at +14.14214V dc.

#### 3-24. Peak AC to DC Convertor

- 3-25. The Peak AC to DC Convertor is a video amplifier which compares the amplitude of the output signal to  $V_{REF}$  and produces a dc voltage equal to four times any negative difference. The circuitry consists of input divider R37 through R42, differential amplifiers U3 and Q8 through Q10, and emitter followers Q11, Q12. A simplified diagram is shown in Figure 3-2.
- 3-26. The input divider R37 through R42 receives the rms output signal and  $V_{REF}$  through S2. The center of this divider is tapped at the junction of R40 and R41 and applied to one input of U3. Unity ratio is made possible at this tap by reversal of the inputs through S2 and adjustment of R37. Except for a small interval of time during the negative most peak of the rms signal, a positive current is flowing into the input of the video amplifier; however, since the input resistance of U3 is extremely high and the current is of proper polarity of forward bias CR9, it is conducted through CR9 and Q11 to -18V. When the peak of the rms signal is more negative than  $V_{REF}$ , the input cur-




Figure 3-2. PEAK AC TO DC CONVERTOR (SIMPLIFIED)

rent reverses direction and CR9 is cut-off. This signal condition is then amplified by U3 and Q8 through Q10, which produces an emitter current in Q12. The resulting current produces a voltage charge on C7 in the A2A1 PCB that is four times the negative peak difference between the rms output and  $V_{REF}$ . Variable resistor R60 allows adjustment of the bias on CR9. R49 allows zero adjustment of the video amplifier input offset voltage.

#### 3-27. Sample and Hold

3-28. The Sample and Hold circuit transfers the charge on C7 in the A2A1 PCB to the input of the Integrator. This circuit is operational only at output frequencies below 20 kHz. It is disabled on output frequencies above 20 kHz because the overall detection is sufficiently fast without sample and hold. The circuitry consists of Schmitt Trigger Q13, Q14, inverter amplifiers Q7 and Q15, Q16, and FET gate Q17.

3-29. Positive excursions of the pulse wave form at the base of Q13 correspond to when CR9 in the Peak AC to DC Convertor is cut-off and a negative peak difference signal is being stored on C7 in the A2A1 PCB. This positive going pulse is shaped by Schmitt Trigger Q13 and Q14. Normally, Q14 is conducting and Q13 is cut-off. Presence of a positive going input to Q13 turns it on and turns off Q14. The resulting positive pulse at the collector of Q14 subsequently has a duration equal to the conduction interval of Q13. This pulse is coupled through C29 and turns on inverter Q15, Q16. The conduction of Q15 and the clamping action of Q16 produces a positive pulse through C8 in

the A2A1 PCB and CR13, which is applied to the gate of Q17. This positive pulse occurs at the trailing edge of the Schmitt Trigger pulse and turns on Q17. Conduction of Q17 then transfers the voltage charge on C7 in the A2A1 PCB to C9, which is at the input of the Integrator. The rectifier action of CR13 and C40 produces a zero volt turn on signal at the gate of Q17 in the absence of pulses from the Schmitt Trigger. This is necessary because the Schmitt Trigger of Q13 and Q14 is disabled on output frequencies above 20 kHz by a jumper between P9 and P17. Inverter Q7 provides a positive pulse to Q17 which compensates for the small error caused by the gate to drain capacitance.

#### 3-30. Integrator

3-31. The Integrator consisting of U4 and associated components produces an amplitude control voltage for the Oscillator that is dependent upon the error signal from Peak AC to DC Convertor. U4 is a high gain, non-inverting amplifier. One input is derived from C9 in the A2A1 PCB and the other from divider R72 through R75. Variable resistor R72 allows offset voltage compensation for U4. The network consisting of CR14 through CR16 and R78 functions as a clamping circuit which limits the maximum output voltage from U4. This circuit improves the recovery time of the Integrator upon initial turn-on and fault (UNCAL) conditions.

#### 3-32. Oscillator

3-33. The Oscillator produces the constant amplitude 10V rms, fixed frequency output signal. It is a bridge "T"

oscillator formed by input amplifier Q18 through Q24, voltage controlled resistor FET Q26, and output amplifier Q25, Q27, Q28. Output amplitude is precisely maintained at 10V rms by the integrator output voltage applied to Q26. Output frequency is dependent upon the component values in the bridge "T" feedback network.

3-34. Input amplifier Q18 through Q24 is the heart of the Oscillator. The differential pair of Q19 and Q21 receives two inputs derived from feedback networks connected to the Oscillator output. The input to the base of the Q19 is through a bridge "T" network in the A2A1 PCB. Component values of A2A1C1 C2, R1 and R2 determine the center output frequency. The input to the base of O21 is through the positive feedback network composed of R95 and R96. This feedback signal together with the conduction level of Q26 controls the output amplitude. Adjustment of R95 and R96 allows offsetting the output frequency. Conduction of Q26 is dependent upon the voltage control signal applied to its gate. This signal is derived from the Integrator and is of such a level as to maintain the output signal at precisely 10V rms. Q18 and Q20 combine the collector signals of Q19 and Q20 in the appropriate phase so that the output signal to Q22 base is twice that of what is normally obtained from a differential input stage. This configuration provides minimum ac current flow in Q19 and Q21. The collector signal at Q23 is the first point at which a 10V rms signal is available. Emitter follower Q24 drives the following output stage of Q27 and Q28. AC current in Q23 and Q24 is minimized by bootstrapping R88 and the emitter load of Q24 through C35 to

the output. Overall open loop forward gain of the input amplifier is determined by the ratio of C33  $(X_c)$  in ratio with the sum of R82 and R83 times two.

3-35. The output amplifier of Q25 and Q27, Q28 is a complementary output stage. Temperature compensation of the bias current for Q27 and Q28 is provided through Q25 and the divider network of R99 through R101. Variable resistor R100 allows adjustment of this bias current. Output amplifiers Q27 and Q28 produce the output signal of the instrument. Maximum output current is limited by the collector load resistors and the supply voltage. The output signal is specified to 10 mA, above which clipping and distortion may result.

#### 3-36. Overload Indicator

- 3-37. The Overload Indicator consists of Q29 and the light emitting diode CR23. This circuit illuminates the UNCAL indicator wherever the output current exceeds 10 mA.
- 3-38. Q29 monitors the voltage drop across R106. When the output current is greater than 10 mA, the voltage drop across R106 will be greater than 0.6 volts. This voltage turns on Q29 whose conduction path is through the UNCAL indicator CR23. Since CR23 acts-similar to a zener, the first 1 mA of collector current of Q29 is bypassed around CR23 through R113. Any further increase in current is through CR23, thus assuring rapid turn on of the UNCAL indicator.

# Section 4 Maintenance

#### 4-1. INTRODUCTION

4-2. This section contains service and maintenance information for the Model 510A. The information is arranged under headings of "SERVICE INFORMATION, GENERAL MAINTENANCE, MAINTENANCE ACCESS, PERFORMANCE CHECKS, CALIBRATION PROCEDURES, COMPENSATING COMPONENT SELECTION, and TROUBLESHOOTING." Equipment required to service this instrument is listed in Table 4-1. If the recommended equipment is not available, substitute equipment having equivalent specifications can be used.

#### 4-3. SERVICE INFORMATION

- 4.4. Each instrument that is manufactured by the John Fluke Mfg. Co., Inc. is warranted for a period of one year upon delivery to the original purchaser. The WARRANTY is located at the front of the manual.
- 4-5. Factory authorized calibration and service for each Fluke product is available at various world-wide locations. A complete list of these authorized service centers is located at the rear of the manual. Shipping information is given in Section 2 paragraph 2-3. If requested, an estimate will be provided to the customer before any repair work is begun on instruments that are beyond the warranty period.

#### 4-6. GENERAL MAINTENANCE

#### 4-7. Cleaning

4-8. The Model 510A should be cleaned periodically to remove accumulation of any dust or other contaminates. The exterior should be cleaned using a cloth moistened with ordinary soap and water. Cleaning of the interior should be done with clean, dry air at low pressure. If the printed circuit boards require cleaning, first spray them with Freon T.F. Degreaser (Miller Stephenson Co., Inc.) and then remove the dirt with clean, dry air at low pressure.

#### 4-9. Fuse Replacement

4-10. Input line power to the instrument is overload protected by a fuse installed on the rear panel. A decal giving the type and rating of the fuse is also located on the rear panel. If replacement is necessary, use only the type fuse specified on the decal for 115 or 230V ac line power.

#### 4-11. Lamp Replacement

4-12. An UNCAL status indicator (LED) is located on the front panel. This indicator is accessible after removing the top dust cover and requires no special tools to replace. If replacement is necessary, use a Fairchild, type FLV 102 (FLUKE PART NO. 309617) or equivalent.

TABLE 41. REQUIRED TEST EQUIPMENT

NOMENCLATURE	RECOMMENDED EQUIPMENT	TEST FUNCTION
Autotransformer	Variac	Performance checks Calibration Troubleshooting
Multimeter	FLUKE 853A	Troubleshooting
AC/DC Differential Voltmeter	FLUKE 887AB	Performance checks Calibration Troubleshooting
DC Voltage Standard/Null Detector	FLUKE 335D	Performance checks Calibration
Thermal Transfer Standard	FLUKE 540B, A54-2 (Certified to ±0.04% at 50 kHz - 100 kHz)	Performance checks Calibration
Frequency Counter	HP 5245L	Performance checks Calibration Troubleshooting
Oscilloscope	Tektronix 543, 1A1, X10 Probe	Calibration Troubleshooting
Resistive Loads	700, 900, 1k ±2% (Usable to 100 kHz)	Performance checks

4-13. Two ballast lamps designated DS1 and DS2 that are part of the -01 Option are installed on the A2 Main PCB. These lamps are mounted in clip holders attached to the inner rear panel. Access to the lamps is provided after removal of the top dust cover. Replacement requires no special tools. If replacement is necessary, use only GE757 (FLUKE PART NO, 175265) or equivalent.

#### 4-14. MAINTENANCE ACCESS

4-15. The following procedure is to be used to gain access to the interior sections of the Model 510A.

#### 4-16. Major Section Access

- a. Turn off the Model 510A and remove the top dust cover. Access is provided to all adjustments and test points shown in Figure 4-1.
- b. Remove the bottom dust cover. Access is now provided to assemblies shown in Figure 4-2.

### 4-17. Plug-In Assembly Removal and Installation

- a. Locate the assembly to be removed using Figure 4-2.
- Disconnect any wiring and then remove mounting screws.
- c. Remove the plug-in assembly using a gentle rocking motion and an even pulling force.
- d. Install the plug-in assembly in its correct position using a gentle rocking motion and steady downward pressure. Ensure that each mating connector is correctly aligned during installation.
- e. Reconnect any wiring disconnected in step c.

  Each wire is labeled with a number which corresponds to a connector on the PCB.




Figure 4-1. ADJUSTMENT AND TEST POINT LOCATIONS




Figure 4-2. ASSEMBLY LOCATIONS (BOTTOM COVER REMOVED)

## 4-18. Battery Removal and Replacement (-01 Option)

- 4-19. The batteries for the -01 Option are installed on the inside of the bottom dust cover as shown in Figure 4-2. If replacement is necessary, the entire Battery Pack, FLUKE PART NO. 284356, should be replaced. Proceed as follows:
- Disconnect the four wires labeled 1 through 4 from A3 Battery Pack PCB. Refer to Figure 4-2 for location.
- b. Remove the screws which secure the Battery Pack to the bottom dust cover and then remove the Battery Pack.
- c. Install a new Battery Pack, FLUKE PART NO. 284356, on the bottom dust cover using the mounting screws removed in step b.
- d. Connect the four Battery Pack wires to the A3
  Battery Pack PCB. Each wire is labeled with a
  number which corresponds to a connector on the
  PCB.

#### 4-20. PERFORMANCE CHECKS

- 4-21. The following checks can be used to verify most electrical specifications on the Model 510A. Each check includes an introduction which states the objectives and lists the required test equipment. Refer to Table 4-1 for the recommended equipment.
- 4-22. Should a trouble be discovered, first determine that the instrument does not require calibration. If calibration does not correct the problem, troubleshoot the instrument and repair as necessary.

#### 4-23. Preliminary Operation

- a. Connect the power cord through an autotransformer to line power. Set the autotransformer output to 115V ac.
- b. Set the POWER switch on the front panel to ON.
  The meter should indicate LINE OPR.
- c. Allow the instrument to operate for at least 10 minutes.

#### 4-24. Line and Load Regulation Checks

- 4-25. This check provides a means of verifying the line and load regulation performance. Line voltage changes should not cause output variations greater than 10 ppm under full load. No load to full load changes should not cause output variations greater than those given in Figure 4-3. The following test equipment is required to perform these checks:
  - 1. Autotransformer
  - 2. AC Differential Voltmeter
  - 3. 1k Resistive Load




Figure 4-3. LOAD REGULATION

- a. Perform the steps given in paragraph 4-23.
- b. Connect the 1k load to the front panel OUTPUT terminals.
- c. Connect an ac differential voltmeter to the front panel OUTPUT terminals and record its indication.
- d. Vary the autotransformer output setting from 102 to 128V ac, observing that the output voltage does not change more than ±100 uV.
- e. Return the autotransformer setting to 115V ac and disconnect the 1k load from the OUTPUT terminals.
- f. Record the OUTPUT terminal voltage with the ac differential voltmeter.
- g. Reconnect the 1k load to the OUTPUT terminals, observing that the output voltage does not change more than the limit specified in Figure 4-3.
- h. Disconnect the test equipment from the front panel OUTPUT terminals.
- Repeat steps b through g at the rear panel OUT-PUT terminals.

j. Disconnect the test equipment.

#### 4-26. UNCAL Indicator Check

- 4-27. This check verifies correct operation of the UN-CAL indicator on the front panel. This indicator should illuminate when the output load current exceeds 10 ma. The test equipment required to perform this check is a 700 and 900 ohm resistive load.
- Connect a 700 ohm load to the OUTPUT terminals, observing that the UNCAL indicator illuminates.
- b. Disconnect the 700 ohm load.
- c. Connect a 900 ohm load to the OUTPUT terminals, observing that the UNCAL indicator remains out.
- d. Disconnect the 900 ohm load.

## 4-28. Frequency Accuracy and Resolution Checks

- 4-29. This check provides a means of verifying the output frequency accuracy and resolution capability. The output frequency should be within  $\pm 0.1\%$  of its specified value. It should be adjustable  $\pm 1\%$  with the FREQUENCY VERNIER control on the front panel. Resolution capability of this adjustment is  $\pm 0.05\%$ . The only equipment required to perform this check is a frequency counter.
- a. Connect the frequency counter to the front panel
   OUTPUT terminals. The output frequency should
   be within ±0.1% of the frequency labeled on the front panel.

#### NOTE!

Use period mode on the frequency counter to increase measurement resolution.

- b. Adjust the FREQUENCY VERNIER control on the front panel to each limit, observing that the output frequency changes ±1%. Resolution with this control should be ±0.05%.
- Adjust the FREQUENCY VERNIER control for the output frequency labeled on the front panel.
- d. Disconnect the frequency counter.

#### 4-30. Output Accuracy Check

4-31. This check provides a means of verifying the amplitude accuracies given in Table 4-2. It consists of two different methods: dc reference and thermal transfer. The test equipment required to perform these checks is listed at the beginning of each method.

TABLE 4-2. OUTPUT AMPLITUDE ACCURACY

	DC REFERENCE			
OUTPUT	AMPLITUDE A	ACCURACY		
FREQ.	FREQ. 30 days 90 day			
50 Hz-5 kHz	±0,01%	±0.02%		
5kHz-10kHz	±0,02%	±0.03%		
10kHz-30kHz	±0.05%	±0.07%		
30kHz-100kHz	±0.15%	±0.17%		

THERMAL TRANSFER					
OUTPUT	AMPLITUDE	ACCURAC	ĊΥ		
FREQ.	24 Hrs	30 days	90 days		
50 Hz-20kHz 20kHz-50kHz 50kHz-100kHz	±0.01% ±0.015% ±0.04%	±0.015% ±0.025% ±0.05%	±0.02% ±0.035% ±0.06%		

#### 4-32. DC REFERENCE.

#### TEST EQUIPMENT:

- 1. DC Voltage Standard/Null Detector
- a. Turn off the Model 510A and remove the top dust cover.
- Make the equipment connections shown in Figure 44.

- c. Set the dc voltage standard output to +14.14214V dc with a null detector sensitivity of 1V.
- d. Turn on the Model 510A and allow it to operate for at least 10 minutes.
- e. Increase the null detector sensitivity and record its indication. Maximum offset is ±140 uV.

f. Turn off the Model 510A and disconnect the test equipment. Replace the upper dust cover.




Figure 4-4. DC REFERENCE EQUIPMENT CONNECTIONS

#### 4-33. THERMAL TRANSFER.

#### TEST EQUIPMENT:

- 1. DC Voltage Standard
- 2. Thermal Transfer Standard (Certified to ± 0.04% at 50 KHz 100 KHz)
- Make the equipment connections shown in Figure 4-5.

- b. Set the dc voltage standard output to 10V dc.
- Perform dc to ac transfer, observing that the thermal transfer, amplitude accuracy given in Table
   4-2 is achieved.
- d. Disconnect the test equipment.




Figure 4-5. THERMAL TRANSFER EQUIPMENT CONNECTIONS

#### 4-34. CALIBRATION PROCEDURES

#### 4-35. Introduction

- 4-36. The Model 510A should be checked for calibration every 24 hours or 60 or 90 days, as desired, or whenever repairs have been made which affect the electrical characteristics. Calibration should be performed after a 10 minute operating period and at an ambient temperature of  $23^{\circ}\text{C} \pm 5^{\circ}$ .
- 4-37. All calibration test points and adjustments are shown in Figure 4-1. These calibration points are accessible after removal of the top dust cover. Required test equipment is listed in Table 4-1.

#### 4-38. Regulator Alignment

a. Remove the top dust cover. Adjustment and test point locations are shown in Figure 4-1.

- b. Connect the power cord through an autotransformer to line power. Set the autotransformer output to 115V ac.
- c. Turn on the Model 510A and allow it to operate for 10 minutes.
- d. Connect the input of a dc voltmeter to TP2 (+) and circuit common.
- e. Adjust +18V (R9) for +18 ±0.2V dc at TP2.
- f. Connect the dc voltmeter input to TP4, observing that the voltage is  $-18 \pm 0.5V$  dc.
- g. Disconnect the dc voltmeter input from TP4.

#### 4-39. Reference Supply Alignment

- a. Make the equipment connections shown in Figure 4-6.
- b. Set the voltage standard output to +14.14214V dc with a null detector sensitivity of IV.
- c. Increase the null detector sensitivity and adjust

V REF (R27) for a 0  $\pm 70$  uV indication on the null detector.

#### NOTE!

If this adjustment cannot be made, refer to paragraph 4-47 for range compensation of R27.

d. Disconnect the test equipment.




Figure 4-6. DC REFERENCE EQUIPMENT CONNECTIONS

#### 4-40. FET Bias

- a. Connect the input of the dc voltmeter to TP5 (+) and circuit common.
- b. Adjust FET BIAS (R90) for  $-2.5 \pm 0.2$ V dc at TP5.
- c. Disconnect the dc voltmeter input from TP5.

#### 4-41. Zero Set

- a. Connect the dc voltmeter input to TP6.
- b. Adjust CONV. OFFSET (R49) for  $0 \pm 100$  uV at TP6.
- c. Connect the dc voltmeter input to TP7.
- d. Adjust INT. OFFSET (R72) for 0 ±100 uV at TP7.
- e. Disconnect the dc voltmeter from the instrument.

#### 4-42. Output Bias

- Connect a shorting jumper between TP13 and circuit common.
- b. Connect the input for a dc voltmeter to TP11 (+) and TP4 (-).
- Adjust OUTPUT BIAS (R100 for +250 mV dc between TP11 and TP4.
- d. Disconnect the dc voltmeter and shorting jumper from the instrument.

#### 4-43. Detector Bias

a. Set the controls of a dc coupled oscilloscope to provide a .01V vertical sensitivity with an established OV reference (Model 510A circuit common) on the display.

- b. Connect the input through X10 probe to TP8.
   Connect the probe ground clip to circuit common.
- Adjust the oscilloscope sweep speed to view at least two complete cycles of the peaked waveform at TP8.
- d. Adjust DET BIAS (R60) until the peak of the waveform is at  $100 \pm 10$  mV in respect to circuit common.
- e. Disconnect the oscilloscope.

#### 4-44. Comparator Balance

- a. Connect the input of an ac differential voltmeter to the front panel OUTPUT terminals.
- Record the ac output voltage.
- c. Switch S2 to the opposite position (white dot not showing) and record the ac voltmeter indication.
- d. Adjust COMP BAL (R37) for a maximum shift of 0 ±50 uV in output voltage of each setting of S2.
- e. Set \$2 to "white dot position" and disconnect the ac differential voltmeter.

#### 4-45. Frequency Adjust

- a. Connect the input of a frequency counter to the front panel OUTPUT terminals. Use period mode for maximum resolution.
- b. Set the FREQUENCY VERNIER control (R96) on the front panel to the center of its adjustment range.
- c. Adjust FREQ. RANGE (R95) for the output frequency labeled on the front panel. If necessary, refine the FREQUENCY VERNIER setting slightly to obtain the appropriate frequency.
- d. Disconnect the frequency counter.

- 4-46. The Model 510A is now calibrated to meet amplitude accuracy specifications related to a dc reference accurate to ±15 ppm. If an amplitude accuracy related to a thermal transfer is required, perform the following procedure:
- a. Make the equipment connections shown in Figure 4-7.
- b. Set the dc voltage standard output to the 10V dc.
- Perform dc to ac transfer, observing the ac amplitude error.

d. Adjust COMP. BAL. (R37) for a 10V rms output from the Model 510A.

#### NOTE!

Transfer accuracy of the thermal transfer standard must be certified to at least  $\pm 0.04\%$  from 50 KHz to 100 KHz.

 e. Disconnect the test equipment and replace the top dust cover. The Model 510A is now fully calibrated.




Figure 4-7. THERMAL TRANSFER EQUIPMENT CONNECTIONS

## 4-47. COMPENSATING COMPONENT SELECTION

- 4-48. Replacement of U2 and associated matched components in the Reference Supply will require selection of jumpers A and B. These jumpers compensate the adjustment range of V REF (R27). Selection of jumpers is done as follows:
- a. Turn off the Model 510A and set V REF (R27) fully counterclockwise.
- Locate jumpers A and B using Figure 4-8 and reconnect any cut jumpers.
- c. Turn on the Model 510A and make the equipment connections shown in Figure 4-6.
- d. Set the voltage standard output to +14.14214V de with a null sensitivity of 1V.




Figure 4-8. V<sub>REF</sub> JUMPER LOCATIONS

- e. Increase the null detector sensitivity and record the offset voltage.
- f. Cut jumpers A and B per Table 4-3.
- g. Adjust V REF (R27) for a  $0 \pm 70$  uV indication on the null detector.

TABLE 4-3. A & B JUMPER SELECTION

OFFSET VOLTAGE (TP 10)	CLIP JUMPER
0 to 0.00571	None
0.00572 to 0.01141	A
0.00142 to 0.01712	В
0.01713 to 0.02182	A and B

#### NOTE!

The Model 510A should be recalibrated using the procedures given in paragraph 4-34 through 4-46.

#### 4-49. TROUBLESHOOTING

4-50. The following information is provided to assist in locating troubles in the Model 510A. It is recommended that the theory of operation in Section 3 be completely understood before attempting any troubleshooting.

#### 4-51. Initial Troubleshooting

- 4-52. Troubleshooting begins by first performing a thorough inspection for improperly scated plug-in assemblies, loose wires, physically damaged parts, or other obvious problems. The next step is to insure that the instrument is being operated correctly, but fails to meet specifications. Performance checks especially designed for this purpose are given in paragraphs 4-20 through 4-33.
- 4-53. Once it is determined that a malfunction exists, all operating voltages should be checked as shown in Figure 4-9. During these checks, the instrument must be operated from nominal line power. If the Rechargeable Battery Pack (-01 Option) is installed, the optional circuitry can be checked using the information in paragraph 4-54.

		-
TEST POINT	VOLTAGE (VDC)	CIRCUITRY CHECKED
1 TP1	+23V	AC INPUT (T1, CR2)
2 TP3	-23V	AC INPUT (T1, CR2)
3 TP4	-18 ±0.5V	–18V REGULATOR
4 TP2	+18 ±0.2V	+18V REGULATOR
5 TP10	+14,14214V	REFERENCE SUPPLY




Figure 4-9. OPERATING VOLTAGE CHECK POINTS

#### 4-54. Rechargeable Battery Pack (-01 Option)

- 4-55. Operating voltages for the optional battery pack circuitry can be checked using the following procedure:
- a. Connect the power cord through an autotransformer to line power. Set the autotransformer output to OV.
- Make the voltage checks on the A3 Battery Pack
   PCB as shown in Figure 4-10.




Figure 4-10. A3 BATTERY PACK PCB CHECKS

- c. Connect the dc voltmeter to A3TP1 and slowly increase the autotransformer output. The voltage at TP1 should increase from +0.1V dc to approximately +25V dc at a line voltage between 30 and 90V ac.
- d. Set the autotransformer output to 115V ac.
- e. Connect the dc voltmeter input to A3TP2 and slowly decrease the autotransformer output. The voltage at TP2 should increase from -25V dc to +0.6V dc at a line voltage between 90 and 30V ac.
- f. Turn off the Model 510A and disconnect the power cord.
- g. Disconnect wire #1 from P1 on the A3 Battery Pack PCB.
- h. Connect the output of a dc power supply set to +24V dc to P1 on the A3 Battery Pack PCB.

- Connect the power supply common to the OUT-PUT LOW terminal on the rear panel.
- i. Turn on the Model 510A and slowly decrease the power supply output until the meter on the front panel swings abruptly to the left.
- j. Record the power supply output voltage. The Model 510A should turn-off at a power supply output between 18.5 and 19.5V dc.
- k. Increase the power supply output until the meter on the front panel abruptly swings to the right. The Model 510A should turn on at a power supply output that is 1.2V above the value recorded in step j.
- 1. Turn off the Model 510A and disconnect the power supply. Reconnect wire #1 to P1 on the A3 Battery Pack PCB.

#### 4-56. Circuit Isolation Checks

4-57. The voltage checks given in Figure 4-11 can be used to isolate a trouble to a major circuit. General troubleshooting of the major circuit should then reveal the exact source of trouble. Circuit voltages are given on the schematic diagram.

	CHECK POINT	NORMAL INDICATION	FAULT ANALYSIS
	1 TP12	10V RMS	IF ABNORMAL CHECK(2), TP5.
	2 TP5	-2.5 ±0.2V dc	A. IF TP12 IS HIGH OR LOW AND TP5 IS ±0.6V, TROUBLE IS IN THE OSCILLATOR.
			B. CHECK(3), TP7, IF TP5 IS AT SOME OTHER VOLTAGE.
	3 TP7	0±100 uV	A. IF TP5 IS NOT +0.6V AND TP7 IS +10 mV OR MORE, TROUBLE IS IN THE INTEGRATOR.
			B. IF TP5 IS MORE POSITIVE THAN  -5V AND TP7 IS10 mV OR  MORE, TROUBLE IS IN THE INTEGRATOR.
			C. IF TP5 IS NOT +0.6V AND TP7 IS OV OR NEGATIVE, TROUBLE IS IN THE PEAK AC TO DC CON- VERTER.
			D. IF TP5 IS MORE POSITIVE THAN  -5V AND TP7 IS OV OR POSITIVE,  TROUBLE IS IN THE PEAK AC TO  DC CONVERTER.
		<u> </u>	NOTE!
			SAMPLE AND HOLD IS CONSIDERED PART OF PEAK AC TO DC CONVER- TER.
	The second second		
		轮叠到	
10 10 10 10 10 10 10 10 10 10 10 10 10 1			***

Figure 4-11. CIRCUIT ISOLATION CHECKS

#### Section 5

## List of Replaceable Parts

#### 5-1. INTRODUCTION

- 5-2. This section contains an illustrated parts breakdown list of the instrument and a Cross Reference List of FLUKE stock numbers to original MANUFACTURERS' part numbers. It also lists recommended spare parts and contains part ordering information. The starting page number of each major listing is given in the Table of Contents.
- 5-3. The parts list shows the location of all assemblies and the replaceable components. Major assemblies are identified by a designation beginning with the letter A followed by a number (e.g., A1 etc). Subassemblies are identified in the same manner; however, the parent assembly designator precedes this designator (e.g., A1A1 etc.). Electrical components are identified by their schematic diagram designator and listed hardware parts are identified by the FLUKE stock number. All listed components are described, and the FLUKE stock number is given. The original MANUFACTURER'S part number for each listed item is given in the Cross Reference List at the rear of this section.

#### 5-4. PARTS LIST COLUMN DESCRIPTIONS

a. The REF DESIG column indexes the item description to the associated illustration. In general the reference designations are listed under each assembly in alpha-numeric order. Subassemblies of minor proportions are sometimes listed with the assembly of which they are a part. In this case, the reference designations may appear out of order.

- b. The DESCRIPTION column describes the salient characteristics of the component. Indention of the description indicates the relationship to other assemblies, components, etc. In many cases it is necessary to abbreviate in this column. For abbreviations and symbols used, refer to Appendix B located at the rear of the manual.
- c. The six-digit part number, by which the item is identified at the John Fluke Mfg. Co., Inc. is listed in the STOCK NO. column. Use this number when ordering parts from the factory or authorized representatives. In the case where a flag note is used, special ordering is required. Flag note explanations are located as close as possible to the flag note.
- d. The TOT QTY column lists the total quantity of the item used in each particular assembly. This quantity reflects only the latest Use Code. Second and subsequent listings of the same item are referenced to the first listing with the abbreviation REF.
- e. Entries in the REC QTY column indicate the recommended number of spare parts necessary to
  support one to five instruments for a period of
  two years. This list presumes an availability of
  common electronic parts at the maintenance site.
  For maintenance for one year or more at an isolated site, it is recommended that at least one of
  each assembly in the instrument be stocked. In

the case of optional subassemblies, plug-ins, etc. that are not always part of the instrument, or are deviations from the basic instrument model, the REC QTY column lists the recommended quantity of the item in that particular assembly.

f. The USE CODE column identifies certain parts which have been added, deleted or modified during the production of the instrument. Each part for which a Use Code has been assigned may be identified with a particular instrument serial number by consulting the Scrial Effectivity List, paragraph 5-9. Sometimes when a part is changed, the new part can and should be used as a replacement for the original part.

#### 5-5. MANUFACTURERS' CROSS REFER-ENCE LIST COLUMN DESCRIPTIONS

- a. The six-digit part number, by which the item is identified at the John Fluke Mfg. Co., Inc. is listed in the FLUKE STOCK NO. column. Use this number when ordering parts from the factory or authorized representatives.
- b. The Federal Supply Code for the item manufacturer is listed in the MFG column. An abbreviated list of Federal Supply Codes is included in Appendix A.
- c. The part number which uniquely identifies the item to the original manufacturer is listed in the MFG PART NO. column. If a component must be ordered by description, the type number is listed.

#### 5-6. HOW TO OBTAIN PARTS

- 5-7. Standard components have been used whenever possible. Standard components may be ordered directly from the manufacturer by using the manufacturer's part number, or parts may be ordered from the John Fluke Mfg. Co., Inc. factory or authorized representative by using the FLUKE stock number. In the event the part you order has been replaced by a new or improved part, the replacement will be accompanied by an explanatory note and installation instructions, if necessary.
- 5-8. You can insure prompt and efficient handling of your order to the John Fluke Mfg. Co., Inc. if you include the following information:

93.4

- a. Quantity.
- b. FLUKE Stock Number.
- c. Description.
- d. Reference Designation.
- e. Instrument model and serial number.

Example: 2 each, 215897, Transistor, 2N4126 A2A1Q1 & Q2 for 645A, S/N 123.

If you must order structural parts not listed in the parts list, describe the part as completely as possible. A sketch of the part, showing its location to other parts of the instrument is helpful.

#### 5-9. SERIAL NUMBER EFFECTIVITY

5-10. A Use Code column is provided to identify certain parts that have been added, deleted or modified during production of the Model 510A. Each part for which a use code has been assigned may be identified with a particular instrument serial number by consulting the Use Code Effectivity List below. All parts with no code are used on all instruments with serial numbers above 123.

USE

CODE

SERIAL NUMBER EFFECTIVITY




Figure 5-1. AC REFERENCE STANDARD

REF DESIG	DESCRIPTION	STOCK NO			USE CODE
	AC REFERENCE STANDARD Figure 5-1	510A			
Al	Front Panel Assembly (Figure 5-2)		1		
A2	Main PCB Assembly (Figure 5-3)	307868	i		
A2A1	PCB Assembly, 50 Hz, 60 Hz, 400 Hz, 1000 Hz, 2400 Hz, 5000 Hz, 19.2 KHz, 100 KHz (Figure 5-4)		1		
A3	Rechargeable Battery Kit (-01 Option) Figure 5-5	$\triangleright$			
A4	Rear Panel Assembly (Figure 5-6)	307892	1	,	1
T1	Xfmr, Power	304097	1		
	Field installation Kit P/N is 510A-01k	1			
,					
			,	i	
	·				
				,	
. 1		, · · · · · · · · · · · · · · · · · · ·			
		,	,		
				,	
		7 - 0			
		' '		<i>)</i>	
					ļ
					}
·					1
					,
		·			[




Figure 5-2. FRONT PANEL ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO			USE CODE
A1	FRONT PANEL ASSEMBLY Figure 5-2	307686	REF		
CR1	Diode, light emitting, 50 mA	309617	1	1	
11	Binding post, red, HI	275552	1		
J2	Binding post, black, LO	275560	1		
13	Binding post, white	275586	i		
M1	Meter, 0-1 mA, ±10%	266494	1		
Sì	Switch, toggle, mini, 3 PDT	284299	1	1	
	Decal, front panel	309351	1		
	Meter, retainer	307322	1		
		:			
	·				
	;				
}					
	•				
					i

Ŕ

H

Á

in the

f l

ř

É




Figure 5-3, MAIN PCB ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	I		USE CODE
A2	MAIN PCB ASSEMBLY Figure 5-3	307868	REF		
C1	Cap, elect, 2 uf +75/-10%, 50V	105197	1	1	
C2, C3	Cap, elect, 250 uf +50/-10%, 40V	178616	2	1	
C4, C5, C7, C9, C28, C32	Cap, Ta, 2.2 uf ±20%, 20V	161927	6	1	
C6, C8, C10, C12 thru C14, C17, C20, C23, C37, C38	Cap, cer, 0.05 uf +80/-20%, 25V	148924	11	1	
C11, C18, C30	Cap, mica, 33 pf ±5%, 500V	160317	3	1	
C15, C21, C22, C24, thru C26, C34, C36	Cap, fixed, cer, 0.01 uf $\pm 20\%$ , 100V	149153	8	1	·
C16	Cap, mica, 4 pf ±5%, 500V	190397	1	1	
C19	Not used				
C27	Cap, mica, 47 pf ±5%, 500V	148536	1	1	
C29	Cap, cer, 180 pf ±10%, 1 kV	105890	1	1	
C31	Cap, cer, 20 pf ±10%, 500V	106369	1	1	
C33	Cap, mica, 10 pf ±10%, 500V	175216	1	1	
C35	Cap, Ta, 4.7 uf ±20%, 20V	161943	1	1	
C39	Cap, Ta, 39 uf ±20%, 20V	163915	1	1	
C40	Cap, Ta, 3.3 uf ±10%, 15V	182808	1,	1	
C41	Cap, cer, 3.3 uf ±10%, 500V	106377	1	1	
C42 CR1, CR7	Cap, cer, var, 1.7 to 10 pF (100 kHz version only) Diode, silicon, 1 amp, 100 piv	321109 116111	1 2	1	
CR2	Diode, bridge, 2 amp, 100 piv	296509	1		
CR3 thru CR6, CR13, thru CR15, CR17, CR18, CR20 thru CR22, CR24	Diode, silicon, 150 MA	203323	13	2	
CR8	Diode, semicon, silicon, 100 MA at 1.5V	161810	1	1	
CR9	Diode, high speed, switching	256339	1	2	 

1

Î

REF DESIG	DESCRIPTION	STOCK NO			USE CODE
CR10, CR11, CR12	Diode, germanium, 80 MA, 100 piv	149187	3		
CR16, CR19	Diode, zener, 6.2V	180497	2	1	
CR23	Not used	į			
DS1, DS2	Lamp, incandesant, 28V, 80 MA	175265	2	1	
Q1, Q5, Q7 thru Q10 Q27	Tstr, silicon, PNP	195974	7	1	
Q2, Q4, Q12 thru Q16, Q24, Q25, Q28	Tstr, silicon, NPN	218396	10	2	
Q3, Q19, Q21	Tstr, semicon, silicon NPN	218081	3	1	
Q6, Q11, Q18, Q20 Q29	Tstr, silicon, PNP	229898	5	l	
Q17, Q26	Tstr, FET, N-channel	261388	2	1	:
Q22, Q23	Tstr, silicon, PNP	225599	2	1	
R1, R2, R65, R67, R78, R87, R91, R92, R109	Tes, comp, 10k ±5%, 1/4w	148106	9		
R3, R7, R16 R68, R107, R108, R113	Res, comp, 1.8k ±5%, 1/4w	175042	7	;	
R4, Ř13, Ř101	Res, comp, 6.8k ±5%, 1/4w	148098	3		
R5, R14, R19	Res, comp, $270\Omega$ $\pm 5\%$ , $1/4w$	160804	3		
R6, R15	Res, comp, 180k ±5%, 1/4w	193441	2		
R8	Res, met flm, $54.9k \pm 1\%$ , $1/8w$	271353	1	l	
R9, R95	Res, var, cermet $10k \pm 10\%$ , $1/2w$	309674	2	Ī	
R10	Res, met flm, $63.4k \pm 1\%$ , $1/8w$	235382	1	1	
R11, R75 R76, R84	Res, comp, 22k ±5%, 1/4w	148130	4		

REF DESIG	DESCRIPTION	STOCK NO		REC QTY	USE CODE
R12, R97	Res, comp, 5.6k ±5%, 1/4w	148080	2		
R17	Res, met flm, 57.6k ±1%, 1/8w	289116	1	1	
R18	Res, met flm, 45.3k ±1%, 1/8w	234971	1	1	
R20	Res, met flm, 51.1k ±1%, 1/8w	309757	1	1	
R21	Res, met flm, 49.9k $\pm 1\%$ , $1/8$ w	293456	1	1	
R22, R23, R30, R31	Res, ref amp, matched set		1	1	
R24	Res, met fim, 2.49k $\pm 1\%$ , 1/8w	309732	1	1	
Ř25	Res, met flm, 1.05k ±1%, 1/8w	293530	1	1	
R26	Res, met flm, $107\Omega \pm 1\%$ , $1/8w$	309716	1	1	
R27	Res, var, $100\Omega \pm 10\%$ , $1/2w$	275735	1		
R28	Res, met flm, $200\Omega \pm 1\%$ , $1/8w$	309724	1	1	
R29	Res, met flm, $10\Omega \pm 1\%$ , $1/8w$	268789	1	1	
R32 thru R36	Not used	·			
R37	Res, var, cermet, $20\Omega$ $\pm 20\%$ , $1/2w$	275727	1	1	
R38	Res, met flm, $40.2\Omega \pm 1\%$ , $1/8w$	245373	ì	1	
R39	Res, met fim, $100\Omega \pm 1\%$ , $1/8w$	168195	1	1	
R40, R41	Res, network (2 resistors)	293506	1	1	
R42	Res, met flm, $33.2\Omega \pm 1\%$ , $1/8w$	199950	1	1	
R43, R54, R57, R64	Res, comp, 100k ±5%, 1/4w	148189	4		
R44, R45 R93	Res, comp, 1k ±5%, 1/4w	148023	3.		

1 2 2 2 2 1 1 1 1	1	CODE
2 2 1 1 1	1	
2 1 1	1	
1		
1	,	
1	,	4
	1	[
_ 1		
5		
1		
1		
2	1	
1		
3		<u>{</u>
2		
1		
1	:	
1		
1		
1		
2	1	
2	1	
1		
1		
ı	1	
	2 2 1	2 1 1 1 1 1 1

,

REF DESIG	DESCRIPTION	<b>STOCK NO</b>		i 1	USE CODE
R94	Res, met flm, $41.2k \pm 1\%$ , $1/8w$	289538	1	1	
R96	Res, var, cermet, $2k \pm 10\%$ , $1/2w$	285163	1	1	
R98	Res, comp, 4.7k ±5%, 1/4w	148072	1		
R100	Res, var, cermet, 2k ±10%, 1/4w	309666	1 .	1	
R102, R104	Res, comp, $5.6\Omega$ $\pm 5\%$ , $1/4w$	208033	2		
R103	Res, comp, $10\Omega \pm 5\%$ , $1/4w$	147868	1		
R106	Res, met flm, $84.5\Omega \pm 1\%$ , $1/8w$	236851	1	1	
R110	Res, comp, 56k ±5%, 1/4w	170738	1		
S1	Switch, double pole, double throw	234278	1	1	
Ŭ1	IC, operational amplifier	2715 <b>02</b>	1	1	
U2	Ref, amp assembly, matched set		1	1	
U3, U4	IC, operational amplifier	284760	2	1	
_	Socket, tstr	285262	25	,	
	R22, R23, R30, R31 and U2 are a matched set. For replacement order ref amp set P/N 4842-307918.				
		,			
		ļ			
			. 1		

Ú,

Į

REF DESIG	DESCRIPTION	STOCK NO	) [	•	USE CODE
A2A1	PCB ASSEMBLY 50 Hz (-02 Option) Figure 5-4	307926	REF		
C1, C2	Cap, fxd, met poly, 0.27 uf ±5%, 100V	310466	2	1	
C3	Cap, Ta, 330 uf ±10%, 6V	193011	1	1	
C4, C5	Cap, Ta, 220 uf ±10% 10V	182840	2	1	
C6	Cap, Ta, 5.6 uf ±10% 6V	198259	1	1	
C7	Cap, Ta, 0.47 uf ±10% 250V	184366	1	1	İ
C8	Cap, cer, 0.025 uf $\pm 2\%$ , 100V	168435	1	1	•
C9	Cap, cer, 0.1 uf ±20%, 100V	149146	1	1	
C10	Cap, plstc 0.1 uf $\pm 10\%$ , 250V	161992	1	1	
J1 thru J19	Amp, receptacle	267617	19	5	
R1	Res, met flm, $2.67k \pm 1\%$ , $1/8w$	312173	1	1	
R2	Res, met flm, 42.2k ±1%, 1/8w	312215	1	1	
R3	Res, comp, 47k ±5%, 1/4w	148163	1		
R4	Res, comp, 2.2M ±5%, 1/4w	198390	1		!

# 2




Figure 5-4. PCB ASSEMBLY, 50 Hz (-02 Option)

REF DESIG	DESCRIPTION	STOCK NO	1	REC	USE CODE
A2A1	PCB Assembly, 60 Hz (-03 Option) Figure 5-5	307934	REF		
C1, C2	Cap, fxd, met poly, 27 uf $\pm 5\%$ , 100V	310466	2	1	
C3	Cap, Ta, 330 uf ± 10%, 6V	193011	1	1	
C4, C5	Cap, Ta, 220 uf ±10%, 10V	182840	2	1	
C6	Cap, Ta, 5.6 uf $\pm 10\%$ , 6V	198259	1	1	
C7	Cap, Ta, 0.47 uf ±10%, 250V	184366	1	1	
C8	Cap, cer, 0.025 uf ±2%, 100V	168435	1	1	
C9	Cap, cer, 0.1 uf ±20%, 100V	149146	1	1	
C10	Cap, plstc, 0.1 uf ±10%, 250V	161992	1	1	
J1 thru J19	Connector, receptacle	267617	19	5	
R1	Res, met flm, 2.21k ±1%, 1/8w	310508	1	1	
R2	Res, met flm, $34.8k \pm 1\%$ , $1/8w$	312181	1	1	
R3	Res, comp, 47k ±5%, 1/4w	148163	1		
R4	Res, comp, 2.2M ±5%, 1/4w	198390	1		
	- · · · · · · · · · · · · · · · · · · ·				

ji.

1

1




Figure 5-5. PCB ASSEMBLY, 60 Hz (-03 Option)

REF DESIG	DESCRIPTION	STOCK NO			USE CODE
A2A1	PCB Assembly, 400 Hz (-04 Option) Figure 5-6	307942	REF		
C1, C2	Cap, fxd, met poly, 0.033 ±5%, 100V	310474	2	1	
C3	Cap, fxd, met poly, 5 uf $\pm 10\%$ , 50V	313254	1	1	:
C4, C5	Cap, Ta, 68 uf ±10%, 15V	182824	2	1	
C6	Cap, Ta, 3.3 uf ±10%, 15V	182808	1	1	
C7	Cap, cer, 0.05 uf ±20%, 100V	149161	1	1	
C8	Cap, mica, 3000 pf ±5%, 500V	161786	1	1	
C9	Cap, fxd, cer, 0.01 uf $\pm 20\%$ , 100V	149153	1	1	
Ji thru J19	Connector, receptacle	267617	19	5	
Rı	Res, mct flm, $2.67k \pm 1\%$ , $1/8w$	312173	1	1	
R2	Res, met flm, 43.2k ±1%, 1/8w	312223	1	1	
R3	Not used				
R4	Res, comp, $2.2M \pm 5\%$ , $1/4w$	198390	1		




Figure 5-6. PCB ASSEMBLY, 400 Hz (-04 Option)

REF DESIG	DESCRIPTION	STOCK NO			USE
A2A1	PCB Assembly, 1000 Hz (-05 Option) Figure 5-7	307959	REF		
C1,C2	Cap, fxd, met poly, 0.015 uf ±5%, 100V	310482	2	1	
C3	Cap, fxd, met poly, 2 uf ±10%, 50V	284687	1	1	
C4, C5	Cap, Ta, 68 uf ±10%, 15V	182824	2	1	ļ
C6	Cap, Ta, 2.2 uf ±20%, 20V	161927	1	1	
C7	Cap, cer, 0.05 uf ±20%, 100V	149161	1	1	
C8	Cap, mica, 1200 pf ± 5%, 500V	148379	1	ī	
C9	Cap, fxd, cer, 0.01 uf $\pm 20\%$ , 100V	149153	1	1	
J1 thru J19	Connector, receptacle	267617	19	5	
Ř1	Res, met flm, 2.43k ±1%, 1/8w	310524	1	1	
R2	Res, met flm, 39.2k ±1%, 1/8w	312207	1	1	
R3	Not used				
R4	Res, comp, $1.2M \pm 5\%$ , $1/4w$	188425	1		




Figure 5-7. PCB ASSEMBLY, 1000 Hz (-05 Option)

REF DESIG	DESCRIPTION	<b>STOCK NO</b>			USE CODE
A2A1	PCB ASSEMBLY, 2400 Hz (-06 Option) Figure 5-8	307967	REF		
C1,C2	Cap, mica, 6200 pf ±5%, 300V	310490	2	1	
C3	Cap, fxd, met poly, 1.0 uf ±10%, 100V	313262	1	1	
C4, C5	Cap, Ta, 68 uf ±10%, 15V	182824	2	1	
C6	Cap, Ta, 0.68 uf ±10%, 35V	182790	1	1	
C7	Cap, cer, 0.05 uf ±20%, 100V	149161	1	1	
C8	Cap, mica, 510 pf ±5%, 500V	148411	1	1	
C9	Cap, Fxd, cer, 0.01 uf ±20%, 100V	149153	1	1	
J1 thru J19	Connector, receptacle	267617	19	5	
RI	Res, met flm, $2.43k \pm 1\%$ , $1/8w$	310524	1	1	
R2	Res, met flm, $39.2k \pm 1\%$ , $1/8w$	312207	1	1	
R3	Not used				
R4	Res, fxd, comp, 750k ±5%, 1/4w	221937	1		
				;	
		·			




Figure 5-8. PCB ASSEMBLY 2400 Hz (-06 Option)

REF DESIG	DESCRIPTION	STOCK NO		ľ	USE CODE
	PCB Assembly, 5000 Hz (-07 Option) Figure 5-9	307975	REF		
C1, C2	Cap, mica, 3000 pf ±5%, 500V	161786	2	1	
C3	Cap, fxd, met poly, 1 uf ±10%, 100V	313262	1	1	
C4, C5	Cap, Ta, 68 uf ±10%, 15V	182824	2	1	
C6	Cap, Ta, .33 uf ±5%, 20V	271338	1	1	
C7	Cap, cer, 0.05 uf $\pm 20\%$ , 100V	149161	1	1,	
C8	Cap, mica, 220 pf ±5%, 500V	170423	1	1	i
C9	Cap, fxd, cer, 0.01 uf $\pm 20\%$ , 100V	149153	1	1	
Il thru J19	Connector, receptacle	267617	19	5	
R1	Res, met flm, $2.43k \pm 1\%$ , $1/8w$	310524	1	1	
R2	Res, met flm, $39.2k \pm 1\%$ , $1/8w$	312207	1	1	
R3	Not used				
R4	Res, comp, 360k $\pm 5\%$ , 1/4w	234690	1		
					J

(4) | 12 | 23

E C

10 N N N




Figure 5-9. PCB ASSEMBLY, 5000 Hz (-07 Option)

REF DESIG	DESCRIPTION	STOCK NO	ı	REC QTY	USE CODE
	PCB Assembly, 19.2 KHz (-08 Option) Figure 5-10	307983	REF		
C1,C2	Cap, mica, 750 pf ±5%, 500V	208983	2	1	
C3	Cap, fxd, met poly, 1 uf ±10%, 100V	313262	1	1	
C4, C5	Cap, Ta, 68 uf ±10%, 15V	182824	2	1	ļ
C6	Cap, plstc, 0.068 uf ±10%, 100V	182170	1	1	
C7	Cap, cer, 0.05 uf ±20%, 100V	149161	1	1	
C8	Cap, mica, 68 pf ±5%, 500V	148510	1	1	
C9	Cap, fxd, cer, 0.01 uf ±20%, 100V	149153	1	1	
J1 thru J19	Connector, receptacle	267617	19	5	
RI	Res, met film, $2.49k \pm 1\%$ , $1/8w$	309732	1	Ţ	
R2	Res, met flm, 39.2k ±1%, 1/8w	312207	1	1	
R3	Not used			]	
R4	Res, comp, 100k ±5%, 1/4w	148189	1	1	1
R5	Not used				
R6	Res, comp. $5.152 \pm 5\%$ , $1/4$ w	281832	1		




Figure 5-10. PCB ASSEMBLY, 19.2 kHz (-08 Option)

REF DESIG	DESCRIPTION	STOCK NO	4		USE CODE
	PCB Assembly, 100 KHz (-09 Option) Figure 5-11	307991	REF	. :	
C1,C2	Cap, mica, 150 pf ±5%, 500V	148478	2	1	
C3	Cap, fxd, met poly, 1 uf ±10%, 100V	313262	1	1	
C4, C5	Cap, Ta, 68 uf ±10%, 15V	182824	2	1	
C6	Cap, cer, 0.05 uf ±20%, 100V	149161	1	1	
C7, C9	Cap, fxd, cer, 0.01 uf ± 20%, 100V	149153	2	1	
C8	Not used				
Ji thru J19	Connector, receptacle	267617	19	5	
R1	Res, fxd, met flm, $2.26k \pm 1\%$ , $1/8w$	310516	1	1	
R2	Res, fxd, met flm, 36.5k ±1%, 1/8w	312199	1	1	
R3	Not used				
R4	Res, comp, $4.7M \pm 5\%$ , $1/4w$	220046	1	1	

.




Figure 5-11, PCB ASSEMBLY, 100 kHz (-09 Option)




Figure 5-12. RECHARGEABLE BATTERY KIT (-01 OPTION)

REF DESIG	DESCRIPTION	STOCK NO	i i		USE
АЗ	RECHARGEABLE BATTERY Kit (-01 Option) Figure 5-12	510A-01K	Ref		
	Battery Pack	307900	1		
BT1, BT2	Battery	284356	1	2	
	Battery Pack PCB	307876	1	1	
CR1	Diode, bridge, 2 amp, 200 piv	296509	1		
CR2, CR6	Diode, zener, 36V ±5%, 1w	284364	2	1	
CR3	Diode, zener, 18.5V	309450	. 1	1	
CR4, CR5	Diode, silicon, 150 mA	203323	2	1	
J1 thru J10	Connector, receptacle	267617	10	3	
P1 thru P4	Connector, post	267500	. 4		
Q1, Q4	Tstr, silicon, PNP	195974	2	1	
Q2, Q5	Tstr, silicon, NPN	218396	2	1	
Q3, Q6	Tstr, semicon, germanium, PNP	148619	2	1.	
R1, R10	Res, comp, 1M ±5%, 1/4w	182204	2		
R2	Res, comp, 15k ±5%, 1/4w	148114	1		
R3	Res, comp, 27k ±5%, 1/4w	148148	. 1		
R4	Res, comp, 150k ±5%, 1/4w	182212	. 1		
R5	Res, comp, 30k ±5%, 4W	193417	1		
R6, R7	Res, comp, 330k ±5%, 4W	192948	2		
R8	Res, comp, 56k ±5%, 4W	170738	1		
R9	Res, comp, 68k ±5%, ¼W	148171	1	:	
	:				

ķ.

Į


12 THE STATE OF TH

Š

ľ

·

k.i



的

Figure 5-13. REAR PANEL ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO		REC QTY	USE CODE
A4	REAR PANEL ASSEMBLY Figure 5-13	307884	REF		
F1	Fuse, fast acting, 1/4 amp, 250V (for 115V operation)	109314	1		
F1	Fuse, fast acting, 1/8 amp, 250V (for 230V operation)	196790			
J1	Connector, male, 3 pin	284166	1		
Ј2	Binding post, white	275586	1		
J3	Binding post, black, LO	275560	1		
J4	Binding post, red, HI	275552	1		
<b>S</b> 1	Switch, slide	226274	1		
XF1	Fuse holder	160846	1		
 	Decal	313064	1		
	Rear panel	307694	1		
	,				
		•			
					ł
	•				
[				1	
					. [
	•			İ	
					l
			1		

2 3!

1

11° 11° 13°

MANUFACTURERS' CROSS REFERENCE LIST					
FLUKE STOCK NO.	MFR.	MFR. PART NO.	FLUKE STOCK NO.	MFR.	MFR. PART NO.
105197	56289	30D205G-050BA4	160804	01121	CB2715
105890	71590	BB60181KS3N	161810	03877	SG5658
106369	32897	831-000-T2HO-200	161927	56289	196D225X0020
106377	32897	861-000-T2H0-3R3	161943	56289	196D475X0020
1166111	05279	1N4817	161992	73445	C280AEA100K
147868	01121	CB1005	163915	56289	196D396X0006
147926	01121	CB1015	168195	91637	TYPE MFF 1/8
148023	01121	CB1025	168229	91637	TYPE MFF1/8
148072	01121	CB4725	168435	56289	C128B101H253M
148080	01121	CB5625	170423	14655	CD15F221J
148098	01121	CB6825	170738	01121	CB5635
148106	01121	CB1035	175042	01121	CB1825
148114	01121	CB1535	175216	14655	CD15C200K
148122	01121	CB1835	175265	08806	757
148130	01121	CB2235	178616	73445	C437ARG250
148148	01121	CB2735	180497	07910	1N753
148163	01121	CB4735	182170	14655	DMF1568
148171	01121	CB6835	182204	01121	CB1055
148189	01121	CB1045	182212	01121	CB1545
148379	14655	CD19F122J	182790	56289	150D684X9035A2
148478	14655	CD15F151J	182808	56289	150D330X9A2
148510	14655	CD15F680J	182824	56289	150D686X9015R2
148536	14655	CD15E470J	182840	56289	150D227X9010S2
148619	01295	2N1303	184366	73445	C280AE/A470K
148924	72982	5855 <b>-Y</b> 5U-5 <b>0</b> 32	188441	01121	CB4745
149146	56289	33C41B6	190397	14655	CD15C40K
149153	56289	C023B101F103M	192948	01121	CB3315
149161	56289	55C23A1	193011	56289	150D330X9006\$2
149187	93332	1N270	193417	01121	CB3035
159731	01121	CB1235	193441	01121	CB1845
160317	14655	CD15E330J	195974	04713	2N3906
160796	01121	CB8225	196790	71400	TYPE AGC

2205

Î

MANUFACTURERS' CROSS REFERENCE LIST						
FLUKE STOCK NO.	MFR.	MFR. PART NO.	FLUKE STOCK NO.	MFR.	MFR. PART NO.	
198390	01121	CB2255	275560	32767	820-45	
199950	91637	TYPE MFF1/8	275586	32767	820-25	
203323	03508	DHD1105	275727	11236	360T200B	
208033	01121	CB5615	275735	11236	360T101A	
208983	14655	CD19F751J	275750	11236	360T102A	
218032	01121	CB5115	276691	11236	360T105A	
218081	04713	MPS6520	281832	01121	CB5105	
218396	04713	2N3904	284166	82389	EAC301	
220046	01121	CB4755	284299	09353	7301	
220541	01121	CB8245	284364	12969	UZ8736	
221911	01121	CB6225	284760	12040	LM308H	
221929	01121	CB3635	285163	11236	360S202A	
221937	01121	CB7545	285262	71785	133-23-92-039	
221945	01121	CB2415	289116	91637	TYPE MFF1/8	
229898	04713	MP\$6522	289538	91637	TYPE MFF1/8	
234690	01121	CB3645	293456	91637	TYPE MFF1/8	
234971	91637	TYPE MFF1/8	293506	18612	310865	
235382	91637	TYPE MFF 1/8	293530	91637	TYPE MFF1/8	
236752	91637	TYPE MFF1/8	293654	91637	TYPE MFF1/8	
236851	91637	TYPE MFF1/8	296509	09423	FB100	
245373	91637	TYPE MFF1/8	309450	15818	TD333379	
256339	28480	5082-2900	309617	31718	FLV102	
260331	91637	TYPE MFF1/8	309666	11236	360T202A	
266494	32539	TYPE TS-10	309674	11236	360T103A	
267393	91637	TYPE MFF1/8	309716	91637	TYPE MFF1/8	
267617	00779	85863-5	309724	91637	TYPE MFF1/8	
268789	91637	TYPE MFF1/8	309732	91637	TYPE MFF1/8	
271338	56289	150DX5020A2	309757	91637	TYPE MFF1/8	
271353	91637	TYPE MFF1/8	310466	01281	X4630W27	
271502	12040	LM301A	310474	01281	X463UW33351	
275552	32767	820-65	310482	01281	X4630W15051	
			310490	14655	CD19F622J	

Ĩ

高麗

i de

1.00 to

7Å 111 141

1 d (12

47 1.3 17

MANUFACTURERS' CROSS REFERENCE LIST					
FLUKE STOCK NO.	MFR.	MFR. PART NO.	FLUKE STOCK NO.	MFR.	MFR. PART NO
210500	91637	TYPE MFF 1/8			
310508					
310524	91637	TYPE MFF1/8			
312173	91637	TYPE MFF1/8			
312181	91637	TYPE MFF1/8			
312207	91637	TYPE MFF1/8			
312215	91637	TYPE MFF1/8			
312223	91637	TYPE MFF1/8			
313262	01281	X4630W10091			
321109	73899	DVJ300A			
		:			
					•

İ

. II.

:

#### Section 6

## Option & Accessory Information

#### 6-1. INTRODUCTION

6-2. This section of the manual contains information pertaining to the accessories and options available for your instrument.

#### 6-3. ACCESSORY INFORMATION

6-4. The accessory information, if applicable, will contain details concerning accessories that may be used with this particular instrument.

#### 6-5. OPTION INFORMATION

6-6. Each of the options available for this instrument, if any, are described separately under headings containing the option number. The option descriptions contain applicable operating and maintenance instructions and field installation procedures. A complete list of replaceable parts for each option is contained at the end of that option description.

#### Accessory

## Rack Mounting Fixtures

#### 6-1. INTRODUCTION

- 6-2. The FLUKE quarter-rack instruments can be installed in a 19 inch equipment rack in various combinations and in conjunction with other FLUKE half-rack instruments. Figure 6-1 shows various mounting configurations.
- 6-3. Instructions for attaching rack mounting brackets are given in Figure 6-2. Figure 6-3 gives instructions for dual, triple, quadruple rack mounting.





Figure 6-1. RACK MOUNTING CONFIGURATIONS

### RACK MOUNTING PROCEDURE FOR MODULAR SERIES INSTRUMENTS



- 1. REMOVE THE FOUR MOLDED FEET AND BAIL FROM BOTTOM COVER.
- 2.REMOVE THE NAMEPLATE DECALS FROM THE FRONT CORNERS.
- 3.REMOVE THE SCREWS FROM CORNERS WHICH MATCH HOLE PATTERNS IN RACK MOUNTING EARS.
- 4. ATTACH RACK MOUNTING EARS WITH PAN HEAD SCREWS (ENCLOSED).

Option -01

## Rechargeable Battery Pack

### OPTION -01 RECHARGEABLE BATTERY PACK

#### INTRODUCTION

6-2. The Rechargeable Battery Pack shown in Figure 6-1 is installed as the -01 Option. It provides at least 16 hours of continuous operation in the absence of line power. The battery is automatically recharged during line operation.




Figure 6-1. 510A-01K BATTERY PACK

#### 6-3. INSTALLATION

- 6-4. The Rechargeable Battery Pack can be ordered installed at the factory during manufacture by requesting the -01 Option. Field installation of this option is also possible at any time. The field installation kit can be obtained by ordering FLUKE KIT 510A-01K. Installation is as follows:
- a. Turn off the Model 510A and disconnect the power cord.
- b. Remove the bottom dust cover,
- c. Install the Battery Pack (BT1, BT2) on the bottom dust cover as shown in Figure 6-2.

- d. Install the Battery Pack PCB in the position shown in Figure 6-2. Ensure that the mating connectors are correctly aligned during installation.
- e. Connect the four (4) Battery Pack wires to the Battery Pack PCB. Each wire is labeled with a number which corresponds to a connector on the PCB.
- f. Install the bottom dust cover.

#### NOTE!

Operating instructions, theory of operation maintenance, and parts list are located in the Model 510A Instruction Manual.





Figure 6-2. BATTERY PACK KIT LOCATIONS

#### DUAL, TRIPLE & QUAD MOUNTING FOR MODULAR SERIES INSTRUMENTS



FLUKE	DESCRIPTION	QUANTITY				
PART NO.		DUAL RACK KIT #304816 #304808 #304782 #304360	TRIPLE RACK KIT #308130	QUAD RACK KIT #304980		
#309708	DUAL RACK MTG. FASTENER	4	8	12		

- I. REMOVE TOP & BOTTOM COVERS FROM BOTH INSTRUMENTS.
- 2. REMOVE NAMEPLATE DECALS FROM CORNERS.
- 3. REMOVE TOP & BOTTOM SCREWS FROM BOTH FRONT & REAR CORNERS ON THE MATING SIDE OF THE INSTRUMENTS.
- 4. INSERT NO. 8-32 DUAL MOUNTING FASTENER, THROUGH THE P-NUTS IN BOTH FRONT & REAR CORNERS.
- 5. REMOVE FEET FROM BOTTOM COVERS AND REPLACE TOP & BOTTOM COVERS.

Figure 6-3. DUAL, TRIPLE AND QUAD MOUNT

# Section 7 General Information

7-1. This section of the manual contains generalized user information as well as supplemental information to the List of Replaceable parts contained in Section 5. The following information is presented in this section:

List of Abbreviations
Federal Supply Codes for Manufacturers
Fluke Technical Service Centers — U.S. and Canada
Sales and Service Locations — International
Sales Representatives — U.S. and Canada

#### List of Abbreviations and Symbols

Aoramp	ampere	Н	henry	pF	picofarad
ac	alternating current	hd	heavy duty	pn	part number
af	audio frequency	hf	high frequency	(+) or pos	positive
a/d	analog-to-digital	Hz	hertz	pot	potentiometer
assy	assembly	1C	integrated circuit	р-р	peak-to-peak
AWG	american wire gauge	if	intermediate frequency	ppm	parts per million
8	bel	in	inch (es)	PROM	programmable read-only
bcd	binary coded decimal	intl	internal		memory
°c	Celsius	I/O	input/output	psi	pound-force per square inc
сар	capacitor	k	kilo (10 <sup>3</sup> )	RAM	random-access memory
cw	counterclockwise	kHz	kilohertz	rf	radio frequency
58f	ceramic	kΩ	kilohm(s)	rms	root mean square
cermet	ceramic to metal(seal)	kV	kilovolt(s)	ROM	read-only memory
skt	circuit	lf.	low frequency	s or sec	second (time)
cm	centimeter	LED	light-emitting diode	scope	oscilloscope
cmrr	common mode rejection	LSB	least significant bit	SH	shield
	ratio		•	Si	silicon
comp	composition	LSD	least significant digit	serno	serial number
•	continue	M	mega (10 <sup>6</sup> )	sr	shift register
cont	cathode-ray tube	m	milli (10 <sup>-3</sup> )	Ta	tantalum
ort	•	mA	milliampere(s)	18	
EW .	clockwise	max	maximum	tb	terminal boar <b>d</b>
d/a	digital-to-analog	mf	metal film	tc	temperature coefficient or
dac	digital-to-analog	MHz	megahertz		temperature compensating
	converter	min	minimum	texo	temperature compensated
∃B	decibel	ពាពា	millimeter		crystal oscillator
de	direct current	rris	millisecond	tp	test point
dmm	digital multimeter	MSB	most significant bit	u or $\mu$	micro (10 <sup>-6</sup> )
dvm	digital voltmeter	MSD	most significant digit	шhf	ultra high frequency
elect	electrolytic	MTBF	mean time between	μs or μs	microsecond(s) (10 <sup>-6</sup> )
ext	éxternal		failures	uut	unit under test
F	farad	MTTR	mean time to repair	V	volt
°F	Fahrenheit	mV	millivolt(s)	v	voltage
FET	Field-effect transistor	ťπv	multivibrator	var	variable
ff	flip-flop	$\Omega$ M	megohm(s)	Vco	voltage controlled oscillate
req	frequency	n	nano (10 <sup>-9</sup> )	∨hf	very high frequency
=\$N	federal stock number	na	not applicable	vlf	very low frequency
3	gram	NC	normally closed	W	watt(s)
3	giga (10 <sup>9</sup> )	(—) or neg	negative	ww	wire wound
ąd	guard	NO NO	normally open	xfmr	transformer
Ge	germanium	ns	nanosecond	xstr	transistor
GHz	gigahertz		operational amplifier	xtal	crystal
	grganerra gvaranteed minimum	opni ampi	pico (10 <sup>-12</sup> )	xtlo	crystal oscillator
Juo v	•	Þ		$\hat{\Omega}$	ohm(s)
our a	value	para 	paragraph		micro (10 <sup>-6</sup> )
Ind	ground	pcb	printed circuit board	$\mu$	micro (10 )

#### Federal Supply Codes for Manufacturers (Continued)

07597 00213 03797 05574 Viking Industries Burndy Corp. Nytronics Comp. Group Inc. Eldema Div. Subsidiary of Nytronics Inc. Formerly Sage Electronics Genisco Technology Corp. Chatsworth, California Tape/Cable Div. Rochester, New York Compton, California Rochester, New York 07792 03877 Replaced by 16258 Transistron Electronic Corp. Lerma Engineering Corp. 05820 Welwyn International, Inc. Wakefield, Massachusetts Northampton, Massachusetts Wakefield Engineering Inc. Westlake, Ohio 03888 Wakefield, Massachusetts 07910 KDI Pyrofilm Corp. Whippany, New Jersey 00656 Teledyne Semiconductor 06001 Formerly Continental Device Aerovox Corp. General Electric Co. New Bedford, Massachusetts Hawthorne, California Electronic Capacitor & Battery Products Dept. 03911 00686 07933 - use 49956 Clairex Electronics Div. Raytheon Co. Film Capacitors, Inc. Passaic, New Jersey Clairex Corp. Mt, Vernon, New York Columbia, South Carolina Semiconductor Div. HQ 06136 Mountain View, California 03980 Replaced by 63743 08225 AMP Inc. Muirhead Inc. Mountainside, New Jersey 06383 Harrisberg, Pennsylvania Industro Transistor Corp. Panduit Corp. Tinley Park, Illinois Long Island City, New York 01121 04009 Allen-Bradley Co. Milwaukee, Wisconsin Arrow Hart Inc. 08261 06473 Spectra Strip Corp. Hartford, Connecticut Bunker Ramo Corp. Amphenol SAMS Div. Garden Grove, California 01281 04062 08530 TRW Electronic Comp. Replaced by 72136 Chatsworth, California Reliance Mica Corp. Semiconductor Operations 04202 Lawndale, California Brooklyn, New York Beede Electrical Instrument Co. Replaced by 81312 Penacook, New Hampshire 08806 01295 04217 General Electric Co. Texas instruments, inc. 06739 Essex International Inc. Ministure Lamp Products Dept. Semiconductor Group Dallas, Texas Electron Corp. Littleton, Colorado Wire & Cable Div. Cleveland, Ohio Anaheim, California 01537 08863 04221 06743 Nylomatic Corp. Norrisville, Pennsylvania Motorola Communications & Aemco, Div. of Clevite Corp. Electronics Inc. Midtex Inc. Mankato, Minnesota Cleveland, Ohio Franklin Park, Illinois 08988 - use 53085 Skottie Electronics Inc. Archbald, Pennsylvania 04222 Components, Inc., Semcor Div. RCL Electronics Inc. Phoenix, Arizona AVX Ceramics Div. Manchester, New Hampshire AVX Corp. Myrtle Beach, Florida 09214 06860 G.E. Co. Semi-Conductor 01730 Gould Automotive Div. Products Dept. Power Semi-Conductor Products OPN Sec. Replaced by 73586 04423 City of Industry, California 01884 - use 56289 Telonic Industries Laguna Beach, California Sprague Electric Co. Dearborn Electronic Div. Vernitron Corp., Piezo Auburn, New York 04645 Electric Div. Formerly Clevite Corp., Piezo 09353 Lockwood, Florida Replaced by 75376 C and K Components Electric Div. 02114 Watertown, Massachusetts 04713 Ferroxcube Corp. Saugerties, New York Bedford, Ohio Motorola Inc. Semiconductor 06980 Products Scientific Components, Inc. Santa Barbara, California 02131 Eimac Div. Phoenix, Arizona Varian Associates San Carlos, California General Instrument Corp. 04946 09922 Harris ASW Div. Standard Wire & Cable Burndy Corp. Norwalk, Connecticut Westwood, Maine Los Angeles, California Ross Milton, Co., The South Hampton, Pennsylvania 02395 05082 09969 Rason Mfg, Co. Brooklyn, New York Replaced by 94988 Dale Electronics Inc. Yankton, S. Dakota 07115 05236 Replaced by 14674 Jonathan Mfg. Co. 10059 Snelgrove, C.R. Co., Ltd. Don Mills, Ontario, Canada Fullerton, California 07138 Barker Engineering Corp. Westinghouse Electric Corp., M3B 1M2 05245 Formerly Amerace, Amerace Electronic Tube Division Components Corp. now ESNA Corp. 02606 Horsehead, New York Corcom, Inc. Chicago, Illinois Kenilworth, New Jersey Fenwal Labs Div, of Travenal Labs. 07233 11236 TRW Electronic Components CTS of Berne Morton Grove, Illinois 05277 Cinch Graphic Berne, Indiana Westinghouse Electric Corp. City of Industry, California 02660 Semiconductor Div. Bunker Ramo Corp., Conn Div. Formerly Amphenol-Borg 11237 07256 Youngwood, Pennsylvania CTS Keene Inc. Paso Robles, California Silicon Transistor Corp. Electric Corp. Broadview, Illinois 05278 Div. of BBF Group Inc. Replaced by 43543 11358 Chelmsford, MA 02799 05279 CBS Electronic Div. 07261 Areo Capacitors, Inc. Southwest Machine & Columbia Broadcasting System Aumet Corp. Newburyport, MN Plastic Co. Glendora, California Chatsworth, California Culver City, Californía 11403 03508 07263 Best Products Co. General Electric Co. 05397 Fairchild Semiconductor Semiconductor Products Union Carbide Corp. Chicago, Illinois Div. of Fairchild Camera Materials Systems Div. New York, New York Syracuse, New York & Instrument Corp. Mountain View, California 03614 Keystone Columbia Inc. 05571 - use 56289 Warren, Michigan Replaced by 71400 Sprague Electric Co. Bircher Co., Inc. 11532 03651 Pacific Div. Rochester, New York Teledyne Relavs Replaced by 44655

Los Angeles, California

Hawthorne, California

#### Federal Supply Codes for Manufacturers (Continued)

11711 General Instrument Corp Rectifier Division Hickville, New York Qualidyne Corp. Santa Clara, California 12014 Chicago Rivet & Machine Co. Bellwood, Illinois National Semiconductor Corp. Danburry, Connecticut 12060 Diodes, Inc. Chatsworth, California 12136 Philadelphia Handle Co. Camden, New Jersey 12300 Potter-Brumfield Division AMF Canada LTD. Guelph, Onatrio, Canada 12223 Presin Co., Inc. Shelton, Connecticut 12327 Freeway Corp. formerly Freeway Washer & Stamping Co. Cleveland, Ohio Budd Co. The, Polychem Products Plastic Products Div. Bridgeport, PA 12615 U.S. Terminals Inc. Cincinnati, Ohio 12617 Hamlin Inc. Lake Mills, Wisconsin 12697 Clarostat Mfg. Co. Dover, New Hampshire James Electronics Chicago, Illinois 12856 Micrometals Sierra Madre, California 12954 Dickson Electronics Corp. Scottsdale, Arizona 12969 Unitrode Corp. Watertown, Massachusetts Thermalloy Co., Inc. Dallas, Texas 13327 Solitron Devices Inc. Tappan, New York 13511 Amphenol Cadre Div. Bunker-Ramo Corp. Los Gatos, California 13606 - use 56289 Sprague Electric Co. Transistor Div. Concord, New Hampshire Replaced by 23732

14099 Semtech Corp. Newbury Park, California 14140 Edison Electronic Div. Mc Grav-Edison Co. Manchester, New Hampshire 14193 Cal-R-Inc, formerly California Resistor, Corp. Santa Monica, California 14298 American Components, Inc. an Insilço Co. Conshohocken, Pennsylvania 14655 Cornell-Dublier Electronics Division of Federal Pacific Electric Co. Govt. Control Dept. Newark, New Jersey Electro Cube Inc. San Gabriel, California 14869 Replaced by 96853 14936 General Instrument Corp. Semi Conductor Products Group Hicksville, New York 15636 Elec-Trol Inc. Saugus, Catifornia 15801 Fenwal Electronics Inc. Div. of Kidde Walter and Co., Inc. Framingham, Massachusetts 158 18 Teledyne Semiconductors, formerly Amelco Semiconductor Mountain View, California 15849 Litton Systems Inc. Useco Div. formerly Useco Inc. Van Nuys, California 15898 International Business Machines Corp. Essex Junction, Vermont 15909 Replaced by 14140 16258 Space-Lok Inc. Burbank, California 16299 Corning Glass Electronic Components Div. Raleigh, North Carolina 16332 Replaced by 28478 16473 Cambridge Scientific Ind. Div, of Chemed Corporation Cambridge, Maryland 16742 Paramount Plastics Fabricators, Inc. Downey, California 16758 Delco Electronics Div. of General Motors Corp. Kokomo, Indiana 17001

Replaced by 71468

17069 Circuit Structures Lab. Burbank, California 17338 High Pressure Eng. Co., Inc. Oklahoma City, Oklahoma Atlantic Semiconductors, Inc. Asbury Park, New Jersey 17856 Siliconix, Inc. Santa Clara, California 17870 Replaced by 14140 Vacted Inc. Maryland Heights, Missouri 18324 Signetics Corp. Sunnyvale, California 18612 Vishay Resistor Products Div. Vishay Intertechnology Inc. Malvern Pennsylvania 18736 Voltronics Corp. Hanover, New Jersey 18927 G T E Sylvania Inc. Precision Material Group Parts Division Titusville, Pennsylvania 19451 Perine Machinery & Supply Co. Seattle, Washington Electro-Midland Corp. Menco-Electra Inc. Mineral Wells, Texas 20584 Enochs Mfg, Inc. Indianapolis, Indiana 20891 Self-Organizing Systems, Inc. Dallas, Texas 21604 Buckeye Stamping Co. Columbus, Ohio 21845 Solitron Devices Inc. Transistor Division Riveria Beach, Florida 22767 ITT Semiconductors Palo Alto, California Product Comp. Corp. Mount Vernon, New York 23732 Tracor Inc. Rockville, Maryland 23880 Stanford Applied Engrag. Santa Clara, California 23936 Pamotor Div., Wm. J. Purdy Co. Burlingame, California 24248 Replaced by 94222 24355 Analog Devices Inc. Norwood, Massachusetts

24655 General Radio Concord, Massachusetts 24759 Lenox-Fugle Electronics Inc. South Plainfield, New Jersey 25088 Siemen Corp. Isilen, New Jersey 25403 Amperex Electronic Corp. Semiconductor & Micro-Circuits Div. Slatersville, Rhode Island 27014 National Semiconductor Coro. Santa Clara, California 27264 Molex Products Downers Grove, Illinois Minnesota Mining & Mfg. Co. Consumer Products Div. St. Paul, Minnesota 28425 Serv-/-Link formerly Bohannan Industries Fort Worth, Texas 28478 Deltrol Controls Div. Deltrol Corporation Milwaukee, Wisconsin Hewlett Packard Co. Corporate H.Q. Palo Alto, California 28520 Heyman Mfg. Co. Kenilworth, New Jersey Monsanto, Co., Inc. Santa Clara, California 29604 Stackpole Components Co. Raleigh, North Carolina 30148 A B Enterprise Inc. Ahoskie, North Carolina 30323 Illinois Tool Works, Inc. Chicago, Illinois 31091 Optimax Inc. Colmar, Pennsylvania 32539 Mura Corp. Great Neck, New York 32787 Griffith Plastic Corp. Burlingame, California 32879 Advanced Mechanical Components Northridge, California 32897 Erie Technological Products, Inc. Frequency Control Div. Carliste, Pennsylvania 32997 Bourns Inc. Trimpot Products Division Riverside, California 33173 General Electric Co. Products Dept. Owensboro, Kentucky

#### Federal Supply Codes for Manufacturers (Continued)

34333 Silicon General Westminister, California 34335 Advanced Micro Devices Sunnyvale, California 34802 Electromotive Inc. Kenilworth, New Jersey Mallory, P.R. & Co., Inc. Indianapolis, Indiana 42498 National Radio Melrose, Massachusetts 43543 Nytronics Inc. Transformer Co, Div. Geneva, New York 44655 Ohmite Mfg, Co. Skokie, Illinois RCA Corp New York, New York 49956 Raytheon Company Lexington, Massachusetts 50088 Mostek Corp. Carrollton, Texas 50579 Litronix Inc. Cupertino, California 51605 Scientific Components Inc. Linden, New Jersey 53021 Sangamo Electric Co. Springfield, Illinois 54294 Cutler-Hammer Inc. formerly Shallcross, A Cutter-Hammer Co. Selma, North Carolina 55026 Simpson Electric Co. Div. of Am. Gage and Mach. Co. Elgin, Illinois 56289 Sprague Electric Co. North Adams, Massachusetts 59474 Superior Electric Co. Bristol, Connecticut 60399 Torin Corp, formerly Torrington Mfg. Co. Torrington, Connecticut 63743 Ward Leonard Electric Co., Inc. Mount Vernon, New York 64834 West Mfg. Co. San Francisco, Californai Weston Instruments Inc. Newark, New Jersey 66150 Winslow Tele-Tronics Inc. Eaton Town, New Jersey 70485

70563 Amperite Company Union City, New Jersey 70903 Belden Corp. Geneva, Illinois 71002 Birnbach Radio Co., Inc. Freeport, LI New York Büssmann Mfg. Div. of McGraw-Edison Co. Saint Louis, Missouri 71450 CTS Corp. Elkhart, Indiana 71468 ITT Cannon Electric Inc. Santa Ana, California 71482 Clare, C.P. & Co. Chicago, Illinois 71590 Centrelab Electronics Div, of Globe Union Inc. Milwaukee, Wisconsin 71707 Coto Coil Co., Inc. Providence, Rhode Island Chicago Miniature Lamp Works Chicago, Illinois 71785 TRW Electronics Components Cinch Connector Operations Div. Elk Grove Village, Chicago, Illinois 72005 Driver, Wilber B., Co. Newark, New Jersey 72092 Replaced by 06980 72136 Electro Motive Mfg. Co. Williamantic, Connecticut 72259 Nytronics Inc. Polham Manor, New Jersey 72619 Dislight Div. Amperex Electronic Corp. Brooklyn, New York 72653 G.C. Electronics Div. of Hydrometals, Inc. Brooklyn, New York 72665 Replaced by 90303 72794 Dzus Fastener Co., Inc. West Islip, New York 72928 Gulton Ind. Inc. Gudeman Div. Chicago, Illinois Erie Tech, Products Inc.

Erie, Pennsylvania

Helipot Division

Fullerton, California

Beckman Instruments Inc.

73138

73293 Hughes Aircraft Co. Electron Dynamics Div. Torrence, California Amperex Electronic Corp. Hicksville, LI, New York 73559 Carling Electric Inc. West Hartford, Connecticut 73586 Circle F Industries Trenton, New Jersey Federal Screw Products, Inc. Chicago, Illinois 73743 Fischer Special Mfg. Co. Cincinnati, Ohio 73899 JFD Electronics Co. Components Corp Brooklyn, New York 73949 Guardian Electric Mfg. Co. Chicago, Illinois 74199 Quan Nichols Co. Chicago, Illinois 74217 Radio Switch Corp. Marlboro, New Jersey 74276 Signalite Div. General Instrument Corp. Neptune, New Jersey 74306 Piezo Crystal Co. Carlisle, Pennsylvania Hoyt Elect, Instr. Works Penacook, New Hampshire 74970 Johnson E.F., Co. Waseca, Minnesota 75042 TRW Electronics Components IRC Fixed Resistors Philadelphia, Pennsylvania 75376 Kurz-Kasch Inc. Dayton, Ohio 75378 CTS Knights Inc. Sandwich, Illinois Kulka Electric Corp. Mount Vernon, New York 75915 Littlefuse Inc. Des Plaines, Illinois 76854 Oak Industries Inc. Switch Div. Crystal Lake, Illinois 77342 AME Inc Potter & Brumfield Div. Princeton Indiana 77638

General Instrument Corp.

Rectifier Division

Brooklyn, New York

77969 Rubbercraft Corp. of CA. LTD. Torrance, California 72129 Shakeproof Div. of Illinois Tool Works Inc. Elgin, Illinois 78277 Sigma Instruments, Inc. South Braintree, Massachusetts 79499 Stackpole Carbon Co. Saint Marys, Pennsylvania 78553 Eaton Corp. Engineered Fastener Div. Tinnerman Plant Cleveland, Ohio 79136 Waldes Kohinoor Inc. Long Island City, New York 79497 Western Rubber Company Goshen, Indiana 79963 Zierick Mfg. Corp. Mt. Kisko, New York 80031 Electro-Midland Corp., Mepco Div. A North American Phillips Co. Morristown, New Jersey LFE Corp., Process Control Div. formerly API Instrument Co. Chesterland, Ohio 80183 - use 56289 Sprague Products North Adams, Massachusetts 80294 Bourns Inc., Instrument Div. Riverside, California Hammarlund Mfg. Co., Inc. Red Bank, New Jersey 80640 Stevens, Arnold Inc. South Boston, Massachusetts 81073 Grayhill, Inc. La Grange, Illinois 81312 Winchester Electronics Div. of Litton Industries Inc. Oakville, Connecticut Therm-O-Disc Inc. Mansfield, Ohio International Rectifier Corp. Los Angeles, California 81590 Korry Mfg. Co. Seattle, Washington 21741 Chicago Lock Co. Chicago, Illinois Palmer Electronics Corp. South Gate, California 82389 Switchcraft Inc. Chicago, Illinois

Atlantic India Rubber Works

Chicago, Illinois

#### Federal Supply Codes for Manufacturers (Concluded)

82415 North American Phillips Controls Corp. Frederick, Maryland

82872 Roanwell Corp. New York, New York

82877 Rotron Inc. Woodstock, New York

82879 ITT Royal Electric Div. Pawtucket, Rhode Island

83003 Varo Inc. Garland, Texas

83058 Carr Co., The United Can Div. of TRW Cambridge, Massachusetts

83298 Bendix Corp. Electric Power Division Estontown, New Jersey

83330 Smith, Herman H., Inc. Brooklyn, New York

83478
Rubbergraft Corp. of America, Inc.
West Haven, Connecticut

83594 Burroughs Corp. Electronic Components Div. Plainfield, New Jersey

83740 Union Carbide Corp. Battery Products Div. formerly Consumer Products Div. New York, New York

84171 Arco Electronics Great Neck, New York

Great Neck, New York 84411 TRW Electronic Components TRW Capacitors

Ogalfala, Nebraska 84613 Fuse Indicator Corp.

Rockvitte, Maryland 84682 Essex International Inc. Industrial Wire Div

Industrial Wire Div. Peabody, Massachusetts 86577

Precision Metal Products, of Malden Inc. Stoneham, Massachusetts

86684
Radio Corp. of America
Electronic Components Div.
Harrison, New Jersey

86928 Seastrom Mfg. Co., Inc. Glendale, California

87034 Illuminated Products Inc. Subsidiary of Oak Industries Inc. Anahiem, California

88219 Gould Inc. Industrial Div. Trenton, New Jersey 88245 Litton Systems Inc. Useco Div. Van Nuys, California

88419 Cornell-Dubilier Electronic Div. Federal Pacific Co. Fuquay-Varian, North Carolina

88486 Plastic Wire & Cable Jewitt City, Connecticut

88690 Replaced by 04217

89536 Fluke, John Mfg. Co., Inc. Seattle, Washington

89730 G.E. Co., Newark Lamp Works Newark, New Jersey

90201 Mallory Capacitor Co. Div of P.R. Mallory Co., Inc. Indianapolis, Indiana

90211 - use 56365 Square D Co. Chicago, Illinois

90215

Best Stamp & Mfg. Co. Kansas City, Missouri 90303

Mallory Battery Co. Div. of Mallory Co., Inc. Tarrytown, New York

91094 Essex International Inc. Suglex/IWP Div. Newmarket, New Hampshire

91293 Johanson Mfg. Co. Boonton, New Jersey

91407 Replaced by 58474

91502 Associated Machine Santa Clara, California

91506 Augat Inc. Attleboro, Massachusetts

91637 Dale Electronics Inc. Columbus, Nebraska

91662 Elco Corp. Willow Grove, Pennsylvania

91737 - use 71468 Gremar Míg, Co., Inc. ITT Cannon/Gremar Santa Ana, California

91802 Industrial Devices, Inc. Edgewater, New Jersey

91833 Keystone Electronics Corp. New York, New York

91836 King's Electronics Co., Inc. Tuckahoe, New York

91929 Honeywell Inc. Micro Switch Div. Freeport, Illinois 91934 Miller Electric Co., Inc. Div of Aunet Woonsocket, Rhode Island 92194 Alpha Wire Corp.

Elizabeth, New Jersey 93332 Sylvania Electric Products

Semiconductor Products Div.

Woburn, Massachusetts 94145 Replaced by 49956 94154 - use 94988

Wagner Electric Corp. Tung-Sol Div. Newark, New Jersey

94222 Southco Inc. formerly South Chester Corp. Lester, Pennsylvania

95146

Alco Electronic Products Inc. Lawrence, Massachusetts 95263 Leccraft Mfg. Co.

Leecraft Mfg, Co. Long Island City, New York 95264 Replaced by 98278

95275 Vitramon Inc. Bridgeport, Connecticut

95303 RCA Corp. Receiving Tube Div. Cincinnati, Ohio 95348

Gordo's Corp. Bloomfield, New Jersey 95354

Methode Mfg. Corp. Rolling Meadows, Illinois 95712

Bendix Corp. Electrical Components Div. Microwave Devices Plant Franklin, Indiana

95987 Weckesser Co. Inc. Chicago, Illinois

96733 San Fernando Electric Míg. Co. San Fernando, California

96853 Gulton Industries Inc. Measurement and Controls Div. formerly Rustrak Instruments Co. Manchester, New Hampshire

96881 Thomson Industries, Inc. Manhasset, New York

97540 Master Mobile Mounts Div. of Whitehall Electronics Corp. Ft. Meyers, Florida

97913 Industrial Electronic Howare Corp. New York, New York

97945 Penwalt Corp, SS White Industrial Products Div. Piscataway, New Jersey 97966 Replaced by 11358 98094 Replaced by 49956 98159 Rubber-Teck, Inc. Gardena, California

98278 Malco A Microdot Co., Inc. Connector & Cable Div. Pasadena, California

98291 Sealectro Corp. Mamaroneck, New York 98388

98388 Royal Industries Products Div. San Diego, California

98743 Replaced by 12749 98925 Replaced by 14433

99120 Plastic Capacitors, Inc. Chicago, Illinois

99217 Bell Industries Elect. Comp. Div. formerly Southern Elect. Div. Burbank, California

99392 STM Oakland, California

99515 ITT Jennings Monrovia Plant Div. of ITT Jennings formerly Marshall Industries Capacitor Div. Monrovia, California

99779 - use 29587 Bunker-Ramo Corp. Barnes Div. Landsdowne, Pennsylvania

99800

American Precision Industries Inc. Delevan Division East Aurora, New York 99942 Centrelab Semiconductor Centrelab Electronics Div. of

Toyo Electronics (R-Ohm Corp.) Irvine, California

Globe-Union Inc.

El Monte, California

National Connector Minneapolis, Minnesota

#### Fluke Technical Service Centers — U.S. and Canada

**United States CALIFORNIA** 

Burbank Fluke Western Tecnical Center Mike Nagy, Service Manager 2020 N. Lincoln St. Zip; 91504 Tel. (213) 849-4641 Fanta Clara
Fluke Western Technical Center
Tom Marshall, Service Manager
2359 De La Cruz Blvd.
Zip: 95050
Tel. (408) 985-1200

COLORADO Denver Fluke Southwestern Technical Center Mel Suelzle, Service Manager 1980 S. Quebec St. Unit 4 Zip: 80231 Tel. (303) 750-1228 FLORIDA

Orlando Fluke S.E. Technical Center Jesse Morse, Service Manger P.O. Box 6578 940 N. Fern Creek Ave. Zip. 3293 Tel. (305) 896-2296

ILLINOIS ILLINGIS
Des Plaines
Fluke Midwestern
Technical Center
Bruce Hunt, Service Manager
1287 N. Rand Road
Zip: 60016
Tel. (312) 298-7470

MARYLAND Kensington Fluke Mideastern Technical Center John Himes, Service Manager 11501 Huff Court Zip: 20795 Tel. (301) 881-5300

MASSACHUSETTS

Lexington
Fluke N.E. Technical Center
Dick Zemba, Service Manager
109 Massachusetts Ave. Zip: 02173 Tel. (617) 861-8620

MINNESOTÁ Minnespolis Fluke Midwestern Fluke Midwestern Technical Center Robert Wayne, Br. Manager 10800 Lyndale Ave. So. Zip: 55420 Tel. (612) 884-4541 **NEW JERSEY** 

Totowa Fluke Eastern Technical Center Al La Fleur, Service Manager 500 Union Blvd. Zip: 07512 Tel. (201) 742-3215

NEW YORK Farmingdale, LI Fluke Eastern Technical Center Charles Vanek, Br. Manager 59Central Ave. Unit 3 Zip: 11735 Tel. (516) 752-1078 Rochester Fluke Eastern Technical Center

Mike Lambert, Br. Service Manager 4515 Culver Road Zip: 14622 Tel. (716) 342-6940 NORTH CAROLINA

Greensboro Fluke S.E. Technical Center Dwain Cox, Service Manager P.O. Box 9619 1310 Beaman Place Zip: 27408 Tel. (919) 273-1918

WASHINGTON Mountlake Terrace John Fluke Mfg. Co., Inc. Bill Fetrow, Tech. Service Spvr. 7001 - 220th Ave. S.W. Zip: 98043

Canada

Tel. (206) 774-2206

ALBERTA

Calgary
Fluke Canadian Technical Center
Dave Racinsky, Service Manager
3829 - 12th St. N.E.
Zip: T2E 6M5
Tel. (403) 261-0780

ONTARIO Mississauga Fluke Canadian Technical Center Herb Duval, Service Manager 6427 Northam Drive Zip: L4V 1J5 Tel. (416) 678-1500

#### Sales and Service Locations — International

Supplied and supported by Fluke (Nederland) B.V., P.O. Box 5053, Zevenheuvelenweg 53, Tilburg, Netherlands.

AUSTRIA

Walter Rekirsch Elektronische Gerate GmbH & Co. KG. Gottfried-Keller-Gasse 2/9 A-1030 Vienna, Austria Tel: 734294, 725746

BELGIUM C.N. Rood S/A 37 Place de Jamblinne de Meux B-1040 Brussels, Belgium Tel: 02-27352135

CYPRUS Chris Radiovision Ltd. P.O. Box 1989 Nicosia, Cyprus Tel: 66121

DENMARK Tage Olsen A/S Teglvaerksgade 37 DK-2100 Copenhagen 0, Denmark Tel: 01-294800 FINLAND

Oy Findip AB Teollisuustie 7 02700 Kauniainen, Finland Tel: 080-502255 FRANCE

M.B. Electronique S.A. Rue Fourney Rue Fourney ZAC de BUC B.P. N° 31 78530 BUC, France Tel: 9563130

GERMAN FEDERAL REPUBLIC

Fluke (Deutschland) GmbH 4-Dusseldorf Meineckestrasse 53 West Germany Tel: 211-450831 Fluke (Deutschland) GmbH 8000 Munich 80 Mutschellestrasse 1 West Germany Tel: 089-433021 GREECE Hellenic Scientific Representations Ltd. 10, Nympheou Street Athens 615, Greece Tel: 021-7792320/705960

ISRAEL R.D.T. Electronics Engineering Ltd. 46, Sokolov Street Ramat Hasharon 47235, Israel

Tel: 483211

ITALY Sistrel S.p.A. Via Giuseppe Armellini No. 37 00143 Rome, Italy Tel: 5915551 Sistrel S.p.A. Via Timavo 66 20099 Sesto S. Giovanni (Milan) Italy Tel: 02-2485233

NETHERLANDS C.N. Rood, B.V. Cort van der Lindenstraat 11-13 Rijswijk (Z.H.) 2100 Netherlands Tel: 070-996860

NORWAY Morgenstierne & Co. A/S Konghellegate 3 P.O. Box 6688, Rodelókka Oslo 5, Norway Tel: 02-356110

**PORTUGAL** Equipamentos De Laboratorio Ltda. P.O. Box 1100 Lisbon 1, Portugal Tel: 019-976551

SPAIN Ataio Ingenieros S.A. Enrique Larreta 10-12 Madrid 16, Spain Tel: 01-7330562

SWEDEN Teleinstrument AB P.O. Box 490 S-162 Vallingby-4 Sweden Sweden Tel: 08-380370

SWITZERLAND Jenatschstrasse I 8002 Zurich, Switzerland Tel: 01 360711

TURKEY M. Süheyl Erkman Necatibey Cad 92/2 Karakoy/Istanbul Turkey Tel: 441546, 447651

UNITED KINGDOM Fluke International Corp. Garnet Close Watford, WD2 4TT, England Tel: 0923-33066

Customers in the following countries:

Bulgaria, Czechoslovakia, Hungary, Poland, Romania, U.S.S.R. and Yugoslavia

Contact: Amtest Associates Ltd., P.O. Box 55, Addlestone, Surrey, KT 15 1DU, England, Tel: 0932-52121.

Supplied and supported by Fluke International Corporation, P.O. Box 43210, Mountlake Terrace, WA 98043.

ARGENTINA

Coasin S.A. Virrey del Pino 4071 Buenos Aires, Argentina Tel: 523185

AUSTRALIA Elmeasco Instrumenta Pty Ltd, P.O. Box 30 Concord, N.S.W. Australia 2137 Tel; (02) 736-2888 Elmeasco Instruments Pty Ltd. P.O. Box 107 Mt. Waverly, VIC. 3149 Australia Tel: 233-4044

BOLIVIA

Consin Bolivia S.R.L. Casilla 7295 La Paz, Bolivia Tel: 40962

BRAZIL

Arotec S.A. Industrial e Comercio Av. Pacaembu 811 Sao Paulo S.P., Brazil

#### CARIBBEAN & CENTRAL AMERICA

West Indies Salos Co. 7360 Northwest 66th Street Miami, FL 33166 Tel: (305) 592-8188

CHILE

Coasin Chile Ltd. Casilla 14588—Correo 15 Santiago, Chile Tel: 396713

COLOMBIA

Assistec Limitada Apartado Aereo 12322 Bogotá 1, Colombia Tel: 419331

ECUADÓR

Protoco Coasin CIA, Ltda. Apartado 228A Quito, Ecuador Tel: 526759

EGYPT

Lotus Engineering Organisation P.O. Box 1252 Cairo, Egypt Tel: 71617 HONG KONG Gilman & Co., Ltd. P.O. Box 56 Hong Kong Tel: 794266

INDIA

Hinditron Services Pvt. Ltd. 69/A L. Jagmohandas Marg Bombay 400 006, India Tel: 365344, 381616

Hinditron Services Pvt. Ltd./ Hinditron Computers Pvt. Ltd. "Hinditron House" 412 Rajmahal Vilas Extension Bangalore 560 006, India Tel: 32852

INDONESIA

P.T. United Dico-Citas Co., Ltd. JLN Penjaringan 39A Jakarta, Indonesia Tel: 21380

**IRAN** 

Irantronix Company Ltd. 20 Salm Road, Rossevelt Avenue Tehran, Iran Tel: 828294, 831564

JAPAN

JAPAN
Toyo Trading Company Ltd.
P.O. Box 5014
Tokyo International
Tokyo 100-81, Japan
Tel: (03) 279-0771

Toyo Trading Company, Ltd. Suzuki Building 2-38 Junkeicho-dori Minami-ku, Osaka, Japan Tel: (06) 262-3471

JORDAN

Trading & Agricultural Development Co. P.O. Box 567 Amman, Jordan Tel: 23052

Advanced Communications Ltd. City House, Wabers Street P.O. Box 30635 Nairobi, Kenya Tel: 31955

KOREA

Asia Science & Co. International P.O. Box 1250 Seoul, Korea Tel: 76-2761

KUWAIT

Tareq Company P.O. Box Safat 20506 Kuwait, Arabian Gulf Tel: 436100, 436045

LEBANON General Marketing Trading & Centracting Company Anis Naouli Street Naouli Building P.O. Box 155.655 Beirut, Lebanon Tel: 319383, 312061

MALAYSIA

O'Contor's (Pte) Ltd. P.O. Box 1197 Kota Kinabalu, Sabah East Malaysia Tel: 54082 Act. 24002 O'Connor's (Pte) Ltd. P.O. Box 91 Petaling Jaya, Selangor West Malaysia Tel: 51563

MEXICO

Mexitek, S.A. Eugenia 408 Department 1 Mexico 12, D.F., Mexico Tel: 5360910

MOROCCO

S.I.E.E.M. Residence Moulay Ismail Readence Moulay Ismail Bat. C. Boulevard Moulay Slimane Rabat, Morocco Tel: 276-64

NEW ZEALAND

W&K McLean Ltd. P.O. Box 3097 Auckland, New Zealand

NIGERIA

Mofat Engineering Co., Ltd. P.O. Box 6369 Lagos, Nigeria PAKISTAN Pak International Operations 505 Muhammadi House-McLeod Road P.O. Box 5323 Karachi, Pakistan

PERU

Importaciones y Representaciones Electronicas S.A. Avda, Franklin D. Roosevelt 105 Lima 1, Peru Tel: 288650

SAUDI ARABIA

Electronic Equipment Marketing Establishment P.O. Box 3750 Riyadh, Saudi Arabia Tel: 32700

SINGAPORE

O'Connor's (Pte) Ltd. 98 Pasir Panjang Road Singapore 5, Singapore Tel: 637944

SOUTH AFRICA

Fluke SA (Pty) Utd. P.O. Box 39797 Bramley Republic of South Africa

Fluke (Pty.) Ltd. 24 Fountain Shopping Ctr. Main Road Rondebosche 7700 Cape Town Republic of South Africa Tel: 651881

TAIWAN

Tatung Company 22 Chungshan North Road 3rd Sec. Talpel, Taiwan Rep. of China Tel: 5215252

THAILAND

Dynamic Supply Engineering R.O.P. No. 56 Ekamai, Sukhumvit 63 Bankok-11, Thailand Tel: 914434, 928532

URUGUAY

Coasin Uruguaya S.R.L. Cerrito 617-4° Piso Montevideo, Uruguay Tel: 917978

VENEZUELA

Coasin C.A. APDO Postal 50939 Sabana Grande No. 1 Caracas 105, Venezuela Tel: 722311

John Fluke Mfg. Co., Inc.

P.O. Box 43210, Mountlake Terrace, WA 98043 Tel: (206) 774-2211 Toll Free: (800) 426-0361 TWX: 910-449-2850 Telex: 32-0013 Cable: Fluke

#### United States

**ALABAMA** Huntsville BCS Associates, Inc. P.O. Box 1273 3322 S. Memorial Parkway Zip: 35807 Tel. (205) 881-6220

ALASKA Anchorage Harry Lang & Associates 1406 W. 47th Ave. Zip: 99503 Tel. (907) 279-5741

ARIZONA Phoenix Barnhill Associates, Inc. 7319 E. Stotson Drive Scottsdale, AZ 85251 Tel. (602) 947-7841

CALIFORNIA

Los Angeles Instrument Specialists Sales Group John Fluke Mfg. Co., Inc. 2020 North Lincoln Street Burbank, CA 91504 Tel. (213) 849-7181 Santa Clara Instrument Specialists Salea Group John Fluke Mfg. Co., Inc. 2359 De La Cruz Blvd.

COLORADO Denver Barnhill Associates, Inc. 1980 S. Quebec Street, Unit 4 Zip: 80231 Tel. (303) 750-1222

Zip: 95050 Tel. (408) 244-1505

CONNECTICUT Hartford Hartford IRI Sales Group John Fluke Mfg. Co., Inc. P.O. Box 518 Glastonbury, CT 06033 Tel. (203) 633-0777

**FLORIDA** Orlando Orlando BCS Associates, Inc. P.O. Box 6578 940 N. Fern Creek Ave. Zip: 32808 Tel. (305) 896-4881

GEORGIA Decatur BCS Associates, Inc. 2522 Tanglewood Road Zip: 30033 Tel: (404) 321-0980

HAWAII Honolulu Industrial Electronics, Inc. P.O. Box 135 646 Queen Street Zip: 96817 Tcl. (808) 533-6095

ILLINOIS Chicago Cozzens & Cudahy Sales Group John Fluke Mfg. Co., Inc. 1301 North Rand Road Des Plaines, IL 60016 Tel. (312) 298-3600

INDIANA INDIANA Indianapolis Cozzens & Cudahy Sales Group John Fluke Mfg. Co., Inc. Port O'Call Executive Center 21 Beachway Drive Zip; 46224 Tel. (317) 244-2456

KANSAS Kansas City, MO Cozzens & Cudahy Sales Group John Fluke Mfg. Co., Inc. 4406 Chouteau Traffic Way Zip: 64117 Tel. (816) 454-5836

KENTUCKY Louisville BCS Associates, Inc. 4506 Freda Way Valley Station, KY 40272 Tel. (502) 935-9634

MARYLAND Baltimore Mid-Atlantic Sales Group John Fluke Mfg. Co., Inc. 11501 Huff Court Kensington, MD 20795 Tel. (301) 881-3370

MASSACHUSETTS Boston Instrument Representatives John Fluke Mfg. Co., Inc. 109 Massachusetts Ave. Lexington, MA 02173 Tel. (617) 861-8620

MICHIGAN Detroit WKM Associates, Inc. 345 Girard Madison Heights, MI 48071 Tel. (313) 588-2300 MINNESOTA Minneapolis Cozzens & Cudahy Sales Group John Fluke Mfg. Co., Inc. 10800 Lyndale Ave. S. Zin, 55400 Zip: 55420 Tel. (612) 884-4336

MISSOURI Kansas City Cozzens & Cudahy Sales Group John Fluke Mfg. Co., Inc. 4406 Chouteau Traffic Way Zip: 64117 Tel. (816) 454-5836

St. Louis Cozzens & Cudahy Cozens & Cudany Sales Group John Fluke Mfg. Co., Inc. P.O. Box 10013 Zip: 63145 Tel. (314) 423-1234

NEW JERSEY **Newark** SBM Representatives Sales Group John Fluke Mfg. Co., Inc. 1519A Stoyvesant Ave. Union, NJ 07083 Tel. (201) 687-8737

NEW MEXICO Albuquerque Barnhill Associates, Inc. 1410-D Wyoming N.E. Zip: 87112 Žip: 87112 Tel. (505) 299-7658

**NEW YORK** New York SBM Representatives Sales Group John Fluke Mfg, Co., Inc. 460 Colfax Avenue Clifton, N.J. Zip: 07013 Tcl. (201) 778-4040

Rochester SBM Representatives Sales Group John Fluke Mfg. Co., Inc. 4515 Culver Road Zip: 14622 Tel. (716) 266-1400

NORTH CAROLINA Greensboro BCS Associates, Inc. P.O. Box 9619 P.O. Box 9619 1310 Beaman Place Zip: 27408 Tel. (919) 273-1918

OHIO Cleveland WKM Associates, Inc. 16141 Puritas Ave. Zip: 44135 Tel. (216) 267-0445 Dayton WKM Associates, Inc. 7913 S. Suburban Road Zip: 45459 Tel. (513) 434-7500

OREGON Boaverton Showalter Instruments Inc. 3800 S.W. Cedar Hills Blvd. Suite 160 Zip: 97005 Tel. (503) 646-5196

PENNSYLVANIA Philadelphia Mid-Atlantic Sales Group John Fluke Mfg. Co., Inc. Suite H 1010 West 8th Avenue King of Prussia, PA 19406 Tel. (215) 265-4040

Pittsburgh WKM Associates, Inc. 90 Clairton Blvd. Zip: 15236 Tel. (412) 892-2953

TEXAS Austin Barnhill Associates, Inc. 1200 Barton Hill, No. 197 Zip: 78704 Tel. (512) 444-2377

Dallas Barnhill Associates, Inc. 908 Business Parkway Richardson, TX 75080 Tel. (214) 231-2573 Houston Barnhill Associates, Inc. 10606 Hempstead Highway Suite 132 Zip: 77092 Tel. (713) 688-9971

VIRGINIA Williamsburg BCS Associates, Inc. 107 Rich Neck Road Zip: 28185 Tel. (804) 877-4053

WASHINGTON Benton City Showalter Instruments, Inc. P.O. Box 828 Zip: 99320 Tel. (509) 588-3472

Seattle Showalter Instruments, Inc. 1521 - 130th N.E. Bellevue, WA 98005 Tel. (206) 455-4922 WASHINGTON, D.C. Baltimore John Fluke Mfg. Co., Inc. 11501 Huff Court Kensington, MD 20795 Tel. (301) 881-3370

For U.S. areas not listed, contact the regional office nearest you or John Fluke Mfg. Co., Inc., Mountlake Terrace,

Canada

ALBERTA

Calgary Allan Crawford Assoc., Ltd. 3829 - 12th Street N.E. Zip: T2E 6M5 Tel. (403) 276-9658 BRITISH COLUMBIA

North Vancouver Allan Crawford Assoc., Ltd. 116 E. Third St., Suite 203 Zip: V7L 1E6 Tel. (604) 980-4831 NOVA SCOTIA

Allan Crawford Assoc Yad Alian Crawford Assoc., Le Suite 201, Townsend Pl. 800 Windmill Rd, Burnside Industrial Park Dartmouth, NS Zip: B3B 1L1 Tel. (902) 469-7865 ONTARIO

Toronto Allan Crawford Assoc., Ltd. 6427 Northam Drive Mississauga, Ont L4V 1J5 Tel. (416) 678-1560 Ottawa Allan Crawford Assoc., Ltd. 1299 Richmond Road Zip: K2B 7Y4 Tol. (613) 829-9651

QUEBEC
Montreal
Allan Crawford Assoc., Ltd.
1330 Marie Victorian Blvd. E.
Longusuil, P.Q. J4G 1A2
Tel. (514) 670-1212

For Canadian areas not listed, contact the regional office nearest you or Allan Crawford Assoc., Ltd., Mississauga, Ontario.

All of the above Fluke Sales Offices carry local stocks of lowcost Digital Multimeters (Models 8000A, 8030A, 8040A), Counters (Model 1900A), Digital Thermometers (Models 2160A, 2170A, 2165A, 2175A) and the Universal Temperature Probe (Model 80T-150). These same products are available from the following distributors:

**Brownell Electronics** Atlanta, GA (404) 762-5181 Charlotte, NC (704) 394-4341 Memphis, TN (901) 323-8554 Nashville, TN (615) 889-8230 Orlando, FL (305) 843-6770 Mobile, AL (205) 479-5405

The Mancib Company Boston, MA (617) 272-9450 Middletown, CT (203) 346-6646

Elmar Electronics San Francisco, CA (415) 961-3611 Denver, CO (303) 287-9611

Pioneer-Standard Cleveland, OH (216) 587-3600 Dayton, OH (513) 236-9900 Indianapolis, IN (317) 849-7300 Pittsburgh, PA (412) 782-2300 Detroit, MI (313) 525-1800

Liberty Electronics El Segundo, CA (213) 322-8100 San Diego, CA (714) 565-9171 Phoenix, AZ (602) 257-1272 Seattle, WA (206) 763-8200 Albuquerque, NM (505) 299-8293 Beaverton, OR (503) 644-4783

# Section 8 Schematic Diagrams

#### TABLE OF CONTENTS

FIGURE NO.	NAME	DRAWING NO.	
8-1.	Model 510A AC Reference Standard	 510A-1002	8-3/8-4





FIG. 8-1 SHT. 2 OF 3






FIGURE 8-1. AC REFERENCE STANDARD (510A-1001/1002)